

NAVYA INFRA

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mrs. P. Anjali | Site: Miyapur, Hyderabad | Built-up area: 1100 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Digging of foundation trenches, ordinary soil	55	cum	261	14,355
2	Refilling excavated soil around foundation	35.6	cum	137	4,877
3	Sand filling under floors, 100mm	10.2	cum	1,461	14,902
2. FOUNDATION & PLINTH					
4	Lean concrete bed below foundation	9.4	cum	5,849	54,981
5	Stone masonry foundation CM 1:6	23.5	cum	4,320	101,520
6	Plinth beam concrete M20 with formwork	5.7	cum	8,260	47,082
7	DPC 50mm thick CC 1:2:4 over plinth	12.2	sqm	343	4,185
3. RCC SUPERSTRUCTURE					
8	M25 grade RCC — columns, beams, slab	31.6	cum	8,357	264,081
9	RCC M25 for staircase and landing	3.5	cum	7,895	27,632
4. REINFORCEMENT					
10	TMT barsD, fabrication and placing	3127.6	kg	71	222,060
5. MASONRY					
11	Burnt clay brick masonry 230 mm in CM 1:6	24.7	cum	5,225	129,058
12	Half brick partition wall 115 mm CM 1:4	40.7	sqm	770	31,339
6. PLASTERING					
13	Inside wall plaster 12mm	186.8	sqm	180	33,624
14	18 mm external plastering, sponge finish	104.7	sqm	293	30,677
7. FLOORING					
15	Floor tiling with vitrified tiles incl. skirting	97	sqm	1,125	109,125
16	Toilet dado ceramic tiling	22.4	sqm	811	18,166
8. WATERPROOFING					
17	Waterproofing treatment to terrace and toilet sunk	64.9	sqm	675	43,808
10. PLUMBING					
19	Water supply piping CPVC, concealed	4.3	set	11,536	49,605
11. ANTI-TERMITE					
20	Anti-termite treatment to foundation and plinth	62.7	sqm	2,259	141,639
12. PAINTING					
21	Interior painting, emulsion, over putty	191.4	sqm	126	24,116
22	Outside weatherproof painting	114.5	sqm	150	17,175
	TOTAL				1,384,007

Payment Schedule

Stage	Payment
Advance on agreement signing	10%
On completion of foundation	12%
On completion of plinth	6%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days. Owner to provide water and electricity.