

SRINIVASA CONSTRUCTIONS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mrs. G. Swathi | Site: Bachupally, Hyderabad | Built-up area: 2200 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Earthwork excavation in ordinary soil, foundation	111.9	cum	260	29,094
2	Back filling and ramming in layers	63.8	cum	155	9,889
3	Sand bed under floor slab	20.4	cum	1,304	26,602
2. FOUNDATION & PLINTH					
4	PCC 1:4:8 with 40mm aggregate below footings	17.4	cum	5,714	99,424
5	Stone masonry foundation CM 1:6	43.5	cum	4,093	178,046
6	Reinforced cement concrete M20 plinth beam	10.9	cum	8,313	90,612
7	DPC layer above plinth level	25.5	sqm	344	8,772
3. RCC SUPERSTRUCTURE					
8	M25 grade RCC — columns, beams, slab	63.6	cum	8,315	528,834
9	Stair case RCC M25 incl. steps	6.5	cum	7,941	51,616
4. REINFORCEMENT					
10	TMT reinforcement bars Fe500, cut bent and placed	5493.1	kg	73	400,996
5. MASONRY					
11	External brick wall 9 inch, cement mortar 1:6	49.2	cum	5,195	255,594
12	Internal brick partition 4.5 inch	94.5	sqm	738	69,741
6. PLASTERING					
13	Internal cement plaster 12mm in CM 1:4	420.1	sqm	170	71,417
14	Outside wall plaster 18mm two coats	208.7	sqm	225	46,958
7. FLOORING					
15	Vitrified tile flooring 600x600 incl. skirting	182.8	sqm	1,048	191,574
16	Wall tiles in bathrooms up to 7 feet	44.9	sqm	798	35,830
8. WATERPROOFING					
17	Waterproofing treatment to terrace and toilet sunk	114.6	sqm	594	68,072
10. PLUMBING					
19	CPVC water supply lines concealed incl. fittings	9.3	set	11,683	108,652
11. ANTI-TERMITE					
20	Anti-termite treatment to foundation and plinth	115	sqm	2,294	263,810
12. PAINTING					
21	Interior emulsion paint two coats over primer	409.9	sqm	131	53,697
22	Exterior emulsion weather coat, two coats	224.7	sqm	151	33,930
	TOTAL				2,623,160

Payment Schedule

Stage	Payment
Advance on agreement signing	10%
On completion of foundation	10%
On completion of plinth	8%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.