

SAI TEJA ENGINEERS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. M. Farhan | Site: Nizampet, Hyderabad | Built-up area: 2450 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Earthwork excavation in ordinary soil, foundation	125.7	cum	251	31,551
2	Back filling and ramming in layers	73.9	cum	143	10,568
3	Filling river sand below flooring 100 mm	24.5	cum	1,449	35,500
2. FOUNDATION & PLINTH					
4	Plain cement concrete 1:4:8 under footings	19.9	cum	5,661	112,654
5	Stone masonry foundation CM 1:6	54.7	cum	3,741	204,633
6	RCC M20 for plinth beam incl. shuttering	12.6	cum	8,176	103,018
7	Damp proof course 50 mm, CC 1:2:4	28.1	sqm	326	9,161
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	62.3	cum	7,914	493,042
9	Stair case RCC M25 incl. steps	7	cum	8,730	61,110
4. REINFORCEMENT					
10	Steel reinforcement TMT incl. binding	6074.9	kg	70	425,243
5. MASONRY					
11	Brickwork in CM 1:6 for external walls, 230mm	62.2	cum	5,145	320,019
12	Half brick partition wall 115 mm CM 1:4	104.6	sqm	692	72,383
6. PLASTERING					
13	12 mm thick internal plastering CM 1:4	432.9	sqm	190	82,251
14	Outside wall plaster 18mm two coats	230.6	sqm	228	52,577
7. FLOORING					
15	Floor tiling with vitrified tiles incl. skirting	222.3	sqm	1,019	226,524
16	Ceramic tile dado in toilets up to 7ft	57	sqm	789	44,973
8. WATERPROOFING					
17	APP membrane waterproofing to terrace slab	136	sqm	613	83,368
9. ELECTRICAL					
18	Electrical points incl. conduit and wiring	108	pt	660	71,280
11. ANTI-TERMITE					
20	Anti-termite treatment to foundation and plinth	130.6	sqm	6,257	817,164
12. PAINTING					
21	Interior emulsion paint two coats over primer	436.3	sqm	137	59,773
22	Exterior weatherproof paint two coats	243.1	sqm	150	36,465
	TOTAL				3,353,257

Payment Schedule

Stage	Payment
Advance on agreement signing	10%
On completion of foundation	12%
On completion of plinth	6%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days. Owner to provide water and electricity.