

LAKSHMI CONSTRUCTIONS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mrs. G. Swathi | Site: Uppal, Hyderabad | Built-up area: 2200 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Digging of foundation trenches, ordinary soil	114.2	cum	262	29,920
2	Back filling and ramming in layers	69.7	cum	150	10,455
3	Sand filling under floors, 100mm	21.4	cum	1,269	27,157
2. FOUNDATION & PLINTH					
4	Lean concrete bed below foundation	18.6	cum	5,343	99,380
5	Stone masonry foundation CM 1:6	45.2	cum	4,044	182,789
6	Plinth beam concrete M20 with formwork	10.1	cum	8,392	84,759
7	DPC 50mm thick CC 1:2:4 over plinth	24.9	sqm	340	8,466
3. RCC SUPERSTRUCTURE					
8	Reinforced cement concrete M25 for slab and beams	58.7	cum	7,513	441,013
9	Reinforced concrete M25 staircase waist slab	6.2	cum	8,825	54,715
4. REINFORCEMENT					
10	TMT reinforcement bars Fe500, cut bent and placed	6216.4	kg	68	422,715
5. MASONRY					
11	Brickwork in CM 1:6 for external walls, 230mm	50.7	cum	4,943	250,610
12	Internal brick partition 4.5 inch	86.4	sqm	779	67,306
6. PLASTERING					
13	Internal cement plaster 12mm in CM 1:4	405.1	sqm	173	70,082
14	18 mm external plastering, sponge finish	230.9	sqm	242	55,878
7. FLOORING					
15	Floor tiling with vitrified tiles incl. skirting	192.5	sqm	1,004	193,270
16	Wall tiles in bathrooms up to 7 feet	45.5	sqm	825	37,538
8. WATERPROOFING					
17	Terrace and sunk waterproofing treatment	116.4	sqm	623	72,517
9. ELECTRICAL					
18	Electrical points incl. conduit and wiring	94.6	pt	617	58,368
10. PLUMBING					
19	Concealed CPVC plumbing lines with fittings	8.3	set	10,805	89,682
11. ANTI-TERMITE					
20	Pre-construction anti termite treatment	130.6	sqm	8,506	1,110,884
12. PAINTING					
21	Two coats acrylic emulsion on inside walls	401.4	sqm	145	58,203
22	Exterior emulsion weather coat, two coats	236.7	sqm	150	35,505
	TOTAL				3,461,212

Payment Schedule

Stage	Payment
Advance on agreement signing	10%
On completion of foundation	10%
On completion of plinth	8%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.