

SAI TEJA ENGINEERS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. B. Yadav | Site: Bachupally, Hyderabad | Built-up area: 2450 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Digging of foundation trenches, ordinary soil	128.2	cum	254	32,563
2	Back filling and ramming in layers	80.7	cum	140	11,298
3	Sand filling under floors, 100mm	25.7	cum	1,398	35,929
2. FOUNDATION & PLINTH					
4	Lean concrete bed below foundation	20.5	cum	5,474	112,217
5	Size stone masonry in CM 1:6 for foundation	50.1	cum	3,781	189,428
6	RCC M20 for plinth beam incl. shuttering	11.4	cum	8,308	94,711
7	Damp proof course 50 mm, CC 1:2:4	28	sqm	336	9,408
3. RCC SUPERSTRUCTURE					
8	Reinforced cement concrete M25 for slab and beams	71.2	cum	8,690	618,728
9	Stair case RCC M25 incl. steps	7.8	cum	7,626	59,483
4. REINFORCEMENT					
10	TMT barsD, fabrication and placing	6706.3	kg	75	502,972
5. MASONRY					
11	Burnt clay brick masonry 230 mm in CM 1:6	58	cum	5,331	309,198
12	Half brick partition wall 115 mm CM 1:4	95.4	sqm	763	72,790
6. PLASTERING					
13	Inside wall plaster 12mm	407.8	sqm	192	78,298
7. FLOORING					
15	Vitrified tile flooring 600x600 incl. skirting	213.6	sqm	1,043	222,785
16	Toilet dado ceramic tiling	56.5	sqm	870	49,155
8. WATERPROOFING					
17	Waterproofing treatment to terrace and toilet sunk	139.7	sqm	623	87,033
9. ELECTRICAL					
18	Electrical points incl. conduit and wiring	113.6	pt	681	77,362
10. PLUMBING					
19	CPVC water supply lines concealed incl. fittings	9.1	set	10,059	91,537
11. ANTI-TERMITE					
20	Anti-termite treatment to foundation and plinth	127.2	sqm	1,307	166,250
12. PAINTING					
21	Interior emulsion paint two coats over primer	417.9	sqm	136	56,834
22	Exterior weatherproof paint two coats	263.2	sqm	143	37,638
	TOTAL				2,915,617

Payment Schedule

Stage	Payment
Advance on agreement signing	25%
On completion of foundation	15%
On completion of plinth	10%
On casting of roof slab	21%
On completion of brickwork & roof	18%
On finishing & handover	11%

Terms: Rates valid 30 days. Owner to provide water and electricity.