

PRAGATI BUILDCON

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mrs. G. Swathi | Site: Kukatpally, Hyderabad | Built-up area: 2000 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Excavation for foundation in ordinary soil incl. disposal	101.1	cum	243	24,567
2	Back filling and ramming in layers	60.2	cum	132	7,946
3	Sand filling under floors, 100mm	21.3	cum	1,449	30,864
2. FOUNDATION & PLINTH					
4	Plain cement concrete 1:4:8 under footings	16.3	cum	5,733	93,448
5	Random rubble masonry in cement mortar 1:6	44.5	cum	3,917	174,306
6	Reinforced cement concrete M20 plinth beam	9.3	cum	7,857	73,070
7	DPC layer above plinth level	22.1	sqm	311	6,873
3. RCC SUPERSTRUCTURE					
8	Reinforced cement concrete M25 for slab and beams	58.2	cum	8,742	508,784
9	RCC M25 for staircase and landing	5.6	cum	8,067	45,175
4. REINFORCEMENT					
10	TMT reinforcement bars Fe500, cut bent and placed	5588.8	kg	69	385,627
5. MASONRY					
11	Burnt clay brick masonry 230 mm in CM 1:6	46.7	cum	5,019	234,387
12	Half brick partition wall 115 mm CM 1:4	84.9	sqm	735	62,402
6. PLASTERING					
13	Internal cement plaster 12mm in CM 1:4	368.5	sqm	181	66,698
14	18 mm external plastering, sponge finish	201.5	sqm	243	48,964
7. FLOORING					
15	Vitrified tile flooring 600x600 incl. skirting	187.5	sqm	1,076	201,750
16	Toilet dado ceramic tiling	46.8	sqm	869	40,669
8. WATERPROOFING					
17	Waterproofing treatment to terrace and toilet sunk	106	sqm	612	64,872
9. ELECTRICAL					
18	Concealed electrical wiring with copper conductor per point	90.8	pt	702	63,742
10. PLUMBING					
19	CPVC water supply lines concealed incl. fittings	7.5	set	10,152	76,140
11. ANTI-TERMITE					
20	Pre-construction anti termite treatment	119.7	sqm	3,144	376,337
12. PAINTING					
21	Two coats acrylic emulsion on inside walls	335.7	sqm	145	48,676
22	Exterior emulsion weather coat, two coats	186.5	sqm	151	28,162
	TOTAL				2,663,459

Payment Schedule

Stage	Payment
Advance on agreement signing	15%
On completion of foundation	8%
On completion of plinth	5%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.