

SRINIVASA CONSTRUCTIONS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. V. Naidu | Site: Patancheru, Hyderabad | Built-up area: 1100 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Excavation for foundation in ordinary soil incl. disposal	57.3	cum	257	14,726
2	Refilling excavated soil around foundation	34.5	cum	149	5,140
3	Sand bed under floor slab	10.2	cum	1,350	13,770
2. FOUNDATION & PLINTH					
4	PCC 1:4:8 with 40mm aggregate below footings	8.4	cum	5,842	49,073
5	Size stone masonry in CM 1:6 for foundation	21.7	cum	4,307	93,462
6	Plinth beam concrete M20 with formwork	5.1	cum	7,828	39,923
7	DPC layer above plinth level	13.5	sqm	313	4,226
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	30.3	cum	7,901	239,400
9	Reinforced concrete M25 staircase waist slab	3.1	cum	8,831	27,376
4. REINFORCEMENT					
10	TMT reinforcement bars Fe500, cut bent and placed	2976.5	kg	70	208,355
5. MASONRY					
11	Burnt clay brick masonry 230 mm in CM 1:6	26	cum	5,575	144,950
12	Half brick partition wall 115 mm CM 1:4	46.5	sqm	713	33,154
6. PLASTERING					
13	12 mm thick internal plastering CM 1:4	185.9	sqm	173	32,161
14	Outside wall plaster 18mm two coats	117.2	sqm	241	28,245
7. FLOORING					
15	Vitrified tile flooring 600x600 incl. skirting	102.4	sqm	1,057	108,237
16	Ceramic tile dado in toilets up to 7ft	23.2	sqm	810	18,792
8. WATERPROOFING					
17	APP membrane waterproofing to terrace slab	56.7	sqm	849	48,138
10. PLUMBING					
19	CPVC water supply lines concealed incl. fittings	4.5	set	10,477	47,146
11. ANTI-TERMITE					
20	Termite proofing to foundation trenches	65.8	sqm	8,691	571,868
12. PAINTING					
21	Interior painting, emulsion, over putty	189.1	sqm	128	24,205
22	Outside weatherproof painting	105.8	sqm	145	15,341
	TOTAL				1,767,688

Payment Schedule

Stage	Payment
Advance on agreement signing	30%
On completion of foundation	15%
On completion of plinth	10%
On casting of roof slab	19%
On completion of brickwork & roof	16%
On finishing & handover	10%

Terms: Rates valid 30 days. Owner to provide water and electricity.