

VENKATESHWARA BUILDERS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. M. Farhan | Site: Bachupally, Hyderabad | Built-up area: 2450 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Digging of foundation trenches, ordinary soil	129.2	cum	240	31,008
2	Back filling and ramming in layers	77.1	cum	168	12,953
3	Sand bed under floor slab	23.9	cum	1,258	30,066
2. FOUNDATION & PLINTH					
4	Plain cement concrete 1:4:8 under footings	18.8	cum	5,643	106,088
5	Stone masonry foundation CM 1:6	47.7	cum	3,812	181,832
6	RCC M20 for plinth beam incl. shuttering	13.2	cum	7,956	105,019
7	DPC 50mm thick CC 1:2:4 over plinth	31.1	sqm	305	9,486
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	64.8	cum	8,610	557,928
9	RCC M25 for staircase and landing	7.3	cum	8,150	59,495
4. REINFORCEMENT					
10	Steel reinforcement TMT Fe 500 incl. binding	6820.3	kg	67	456,960
5. MASONRY					
11	Burnt clay brick masonry 230 mm in CM 1:6	58.4	cum	5,407	315,769
12	Internal brick partition 4.5 inch	96.6	sqm	768	74,189
6. PLASTERING					
13	12 mm thick internal plastering CM 1:4	441.5	sqm	179	79,028
14	18 mm external plastering, sponge finish	227.3	sqm	242	55,007
7. FLOORING					
15	Vitrified tiles 2x2 ft laid on cement bed	205.6	sqm	986	202,722
16	Wall tiles in bathrooms up to 7 feet	52	sqm	822	42,744
8. WATERPROOFING					
17	Terrace and sunk waterproofing treatment	136.9	sqm	623	85,289
9. ELECTRICAL					
18	Electrical points incl. conduit and wiring	110.4	pt	618	68,227
10. PLUMBING					
19	Water supply piping CPVC, concealed	10.2	set	10,220	104,244
11. ANTI-TERMITE					
20	Pre-construction anti termite treatment	132	sqm	950	125,400
12. PAINTING					
21	Interior emulsion paint two coats over primer	437	sqm	136	59,432
22	Outside weatherproof painting	239	sqm	157	37,523
	TOTAL				2,800,409

Payment Schedule

Stage	Payment
Advance on agreement signing	10%
On completion of foundation	12%
On completion of plinth	6%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days. Owner to provide water and electricity.