

NAVYA INFRA

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. M. Farhan | Site: Uppal, Hyderabad | Built-up area: 1400 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Earthwork excavation in ordinary soil, foundation	77.1	cum	264	20,354
2	Refilling excavated soil around foundation	46.3	cum	152	7,038
3	Sand bed under floor slab	14.6	cum	1,421	20,747
2. FOUNDATION & PLINTH					
4	PCC 1:4:8 with 40mm aggregate below footings	10.7	cum	5,287	56,571
5	Size stone masonry in CM 1:6 for foundation	28	cum	3,770	105,560
6	Reinforced cement concrete M20 plinth beam	6.6	cum	8,433	55,658
7	DPC layer above plinth level	16.4	sqm	298	4,887
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	40	cum	7,928	317,120
9	Stair case RCC M25 incl. steps	4	cum	8,465	33,860
4. REINFORCEMENT					
10	Steel reinforcement TMT Fe 500 incl. binding	3951.6	kg	68	268,709
5. MASONRY					
11	Brickwork in CM 1:6 for external walls, 230mm	35.1	cum	5,314	186,521
12	Half brick partition wall 115 mm CM 1:4	54.2	sqm	694	37,615
6. PLASTERING					
13	12 mm thick internal plastering CM 1:4	265	sqm	177	46,905
14	18 mm external plastering, sponge finish	140.8	sqm	235	33,088
7. FLOORING					
15	Floor tiling with vitrified tiles incl. skirting	131.4	sqm	998	131,137
16	Toilet dado ceramic tiling	30	sqm	880	26,400
8. WATERPROOFING					
17	Terrace and sunk waterproofing treatment	84.1	sqm	583	49,030
9. ELECTRICAL					
18	Concealed electrical wiring with copper conductor per point	65.5	pt	659	43,164
10. PLUMBING					
19	Concealed CPVC plumbing lines with fittings	5.3	set	10,981	58,199
11. ANTI-TERMITE					
20	Pre-construction anti termite treatment	73.4	sqm	4,820	353,788
12. PAINTING					
21	Two coats acrylic emulsion on inside walls	240.1	sqm	134	32,173
22	Outside weatherproof painting	129.3	sqm	147	19,007
	TOTAL				1,907,531

Payment Schedule

Stage	Payment
Advance on agreement signing	15%
On completion of foundation	8%
On completion of plinth	5%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.