

VENKATESHWARA BUILDERS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. K. Srinivas | Site: Kompally, Hyderabad | Built-up area: 1650 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Excavation for foundation in ordinary soil incl. disposal	83.3	cum	264	21,991
2	Backfilling with excavated earth, watered and rammed	47.9	cum	149	7,137
3	Sand bed under floor slab	16.5	cum	1,471	24,272
2. FOUNDATION & PLINTH					
4	Lean concrete bed below foundation	13.6	cum	5,559	75,602
5	Stone masonry foundation CM 1:6	36.1	cum	3,956	142,812
6	RCC M20 for plinth beam incl. shuttering	7.6	cum	11,009	83,668
7	DPC layer above plinth level	20.6	sqm	336	6,922
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	42	cum	8,753	367,626
9	RCC M25 for staircase and landing	5.3	cum	8,589	45,522
4. REINFORCEMENT					
10	TMT bars Fe500D, fabrication and placing	4066.4	kg	76	309,046
5. MASONRY					
11	Brickwork in CM 1:6 for external walls, 230mm	40.9	cum	4,943	202,169
12	Internal brick partition 4.5 inch	70.5	sqm	673	47,446
6. PLASTERING					
13	Inside wall plaster 12mm	272.6	sqm	189	51,521
14	Outside wall plaster 18mm two coats	153.2	sqm	257	39,372
7. FLOORING					
15	Vitrified tile flooring 600x600 incl. skirting	155.8	sqm	1,015	158,137
16	Wall tiles in bathrooms up to 7 feet	36.7	sqm	794	29,140
8. WATERPROOFING					
17	Terrace and sunk waterproofing treatment	96.4	sqm	610	58,804
9. ELECTRICAL					
18	Internal concealed wiring, copper, per point	77.9	pt	623	48,532
11. ANTI-TERMITE					
20	Pre-construction anti termite treatment	92	sqm	3,550	326,600
12. PAINTING					
21	Two coats acrylic emulsion on inside walls	278.6	sqm	139	38,725
22	Outside weatherproof painting	169.2	sqm	150	25,380
	TOTAL				2,110,424

Payment Schedule

Stage	Payment
Advance on agreement signing	30%
On completion of foundation	15%
On completion of plinth	10%
On casting of roof slab	19%
On completion of brickwork & roof	16%
On finishing & handover	10%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.