

LAKSHMI CONSTRUCTIONS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. K. Srinivas | Site: Nizampet, Hyderabad | Built-up area: 2000 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Digging of foundation trenches, ordinary soil	101.1	cum	266	26,893
2	Refilling excavated soil around foundation	66.5	cum	138	9,177
3	Sand filling under floors, 100mm	19.9	cum	1,320	26,268
2. FOUNDATION & PLINTH					
4	Lean concrete bed below foundation	15.7	cum	5,761	90,448
5	Size stone masonry in CM 1:6 for foundation	41	cum	3,772	154,652
6	Plinth beam concrete M20 with formwork	9.8	cum	9,482	92,924
7	Damp proof course 50 mm, CC 1:2:4	25.3	sqm	340	8,602
3. RCC SUPERSTRUCTURE					
8	M25 grade RCC — columns, beams, slab	49.7	cum	7,817	388,505
9	Stair case RCC M25 incl. steps	5.7	cum	8,497	48,433
4. REINFORCEMENT					
10	TMT reinforcement bars Fe500, cut bent and placed	5132	kg	70	359,240
5. MASONRY					
11	Burnt clay brick masonry 230 mm in CM 1:6	50.8	cum	5,745	291,846
12	Brickwork in CM 1:4 for internal partitions, 115mm	80	sqm	753	60,240
6. PLASTERING					
13	Internal cement plaster 12mm in CM 1:4	350.9	sqm	175	61,407
14	External cement plaster 18mm in CM 1:4, two coats	187.1	sqm	253	47,336
7. FLOORING					
15	Floor tiling with vitrified tiles incl. skirting	177.2	sqm	986	174,719
16	Ceramic tile dado in toilets up to 7ft	43.1	sqm	779	33,575
8. WATERPROOFING					
17	APP membrane waterproofing to terrace slab	105.8	sqm	595	62,951
9. ELECTRICAL					
18	Electrical points incl. conduit and wiring	93.5	pt	674	63,019
10. PLUMBING					
19	Concealed CPVC plumbing lines with fittings	8.5	set	10,108	85,918
11. ANTI-TERMITE					
20	Pre-construction anti termite treatment	119.8	sqm	2,229	267,034
12. PAINTING					
21	Two coats acrylic emulsion on inside walls	337.3	sqm	129	43,512
22	Exterior emulsion weather coat, two coats	208	sqm	150	31,200
	TOTAL				2,427,899

Payment Schedule

Stage	Payment
Advance on agreement signing	25%
On completion of foundation	15%
On completion of plinth	10%
On casting of roof slab	21%
On completion of brickwork & roof	18%
On finishing & handover	11%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.