

SRINIVASA CONSTRUCTIONS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. K. Srinivas | Site: Miyapur, Hyderabad | Built-up area: 2000 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Excavation for foundation in ordinary soil incl. disposal	103.7	cum	248	25,718
2	Back filling and ramming in layers	65.5	cum	144	9,432
3	Sand filling under floors, 100mm	20.5	cum	1,351	27,696
2. FOUNDATION & PLINTH					
4	PCC 1:4:8 with 40mm aggregate below footings	15.7	cum	6,032	94,702
5	Random rubble masonry in cement mortar 1:6	42.7	cum	3,863	164,950
6	Reinforced cement concrete M20 plinth beam	10	cum	7,937	79,370
7	DPC 50mm thick CC 1:2:4 over plinth	22.9	sqm	318	7,282
3. RCC SUPERSTRUCTURE					
8	M25 grade RCC — columns, beams, slab	57.5	cum	8,093	465,348
9	Stair case RCC M25 incl. steps	5.8	cum	7,705	44,689
4. REINFORCEMENT					
10	TMT reinforcement bars Fe500, cut bent and placed	5759	kg	75	431,925
5. MASONRY					
11	Burnt clay brick masonry 230 mm in CM 1:6	51.1	cum	5,701	291,321
12	Internal brick partition 4.5 inch	74.2	sqm	762	56,540
6. PLASTERING					
13	Internal cement plaster 12mm in CM 1:4	348.3	sqm	173	60,256
14	External cement plaster 18mm in CM 1:4, two coats	208.5	sqm	253	52,750
7. FLOORING					
15	Floor tiling with vitrified tiles incl. skirting	189.9	sqm	1,118	212,308
16	Ceramic tile dado in toilets up to 7ft	44.2	sqm	878	38,808
8. WATERPROOFING					
17	Terrace and sunk waterproofing treatment	120.6	sqm	660	79,596
9. ELECTRICAL					
18	Electrical points incl. conduit and wiring	88.2	pt	657	57,947
11. ANTI-TERMITE					
20	Anti-termite treatment to foundation and plinth	109.4	sqm	5,984	654,650
12. PAINTING					
21	Interior painting, emulsion, over putty	336.2	sqm	143	48,077
22	Outside weatherproof painting	189.9	sqm	144	27,346
	TOTAL				2,930,711

Payment Schedule

Stage	Payment
Advance on agreement signing	10%
On completion of foundation	10%
On completion of plinth	8%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.