

PRAGATI BUILDCON

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. S. Reddy | Site: Medchal, Hyderabad | Built-up area: 2450 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Earthwork excavation in ordinary soil, foundation	119.9	cum	245	29,376
2	Back filling and ramming in layers	73.9	cum	195	14,411
3	Filling river sand below flooring 100 mm	25.1	cum	1,271	31,902
2. FOUNDATION & PLINTH					
4	Plain cement concrete 1:4:8 under footings	19	cum	5,880	111,720
5	Size stone masonry in CM 1:6 for foundation	50.6	cum	3,946	199,668
6	Plinth beam concrete M20 with formwork	13.1	cum	8,420	110,302
7	DPC 50mm thick CC 1:2:4 over plinth	27.6	sqm	305	8,418
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	65.2	cum	8,666	565,023
9	Reinforced concrete M25 staircase waist slab	7.4	cum	7,799	57,713
4. REINFORCEMENT					
10	TMT barsD, fabrication and placing	6677.9	kg	68	454,097
5. MASONRY					
11	Burnt clay brick masonry 230 mm in CM 1:6	59.8	cum	5,672	339,186
12	Half brick partition wall 115 mm CM 1:4	98.3	sqm	759	74,610
6. PLASTERING					
13	12 mm thick internal plastering CM 1:4	435.8	sqm	180	78,444
14	Outside wall plaster 18mm two coats	227.9	sqm	233	53,101
7. FLOORING					
15	Vitrified tiles 2x2 ft laid on cement bed	218	sqm	1,056	230,208
16	Ceramic tile dado in toilets up to 7ft	55.1	sqm	802	44,190
8. WATERPROOFING					
17	APP membrane waterproofing to terrace slab	131.9	sqm	650	85,735
9. ELECTRICAL					
18	Concealed electrical wiring with copper conductor per point	103.2	pt	712	73,478
11. ANTI-TERMITE					
20	Anti-termite treatment to foundation and plinth	135.7	sqm	833	113,038
12. PAINTING					
21	Interior emulsion paint two coats over primer	442.7	sqm	137	60,650
22	Exterior emulsion weather coat, two coats	261.8	sqm	146	38,223
	TOTAL				2,773,493

Payment Schedule

Stage	Payment
Advance on agreement signing	10%
On completion of foundation	10%
On completion of plinth	8%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days. Owner to provide water and electricity.