

AKSHAYA HOMES

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. K. Srinivas | Site: Kompally, Hyderabad | Built-up area: 1100 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Excavation for foundation in ordinary soil incl. disposal	55.4	cum	262	14,515
2	Back filling and ramming in layers	34.8	cum	143	4,976
3	Sand bed under floor slab	11	cum	1,430	15,730
2. FOUNDATION & PLINTH					
4	Plain cement concrete 1:4:8 under footings	8.9	cum	5,300	47,170
5	Size stone masonry in CM 1:6 for foundation	24	cum	4,184	100,416
6	RCC M20 for plinth beam incl. shuttering	5.5	cum	7,657	42,114
7	DPC layer above plinth level	12.8	sqm	337	4,314
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	28.2	cum	7,789	219,650
9	Reinforced concrete M25 staircase waist slab	3.3	cum	8,201	27,063
4. REINFORCEMENT					
10	TMT barsD, fabrication and placing	2897.3	kg	65	188,324
5. MASONRY					
11	External brick wall 9 inch, cement mortar 1:6	28	cum	5,078	142,184
12	Internal brick partition 4.5 inch	42.1	sqm	754	31,743
6. PLASTERING					
13	Internal cement plaster 12mm in CM 1:4	196.9	sqm	174	34,261
14	External cement plaster 18mm in CM 1:4, two coats	113.9	sqm	261	29,728
7. FLOORING					
15	Vitrified tiles 2x2 ft laid on cement bed	103.6	sqm	1,125	116,550
16	Ceramic tile dado in toilets up to 7ft	24.2	sqm	870	21,054
8. WATERPROOFING					
17	Waterproofing treatment to terrace and toilet sunk	62.5	sqm	621	38,812
9. ELECTRICAL					
18	Electrical points incl. conduit and wiring	51.6	pt	694	35,810
10. PLUMBING					
19	CPVC water supply lines concealed incl. fittings	4.5	set	11,195	50,378
11. ANTI-TERMITE					
20	Anti-termite treatment to foundation and plinth	65.7	sqm	8,958	588,541
12. PAINTING					
21	Interior emulsion paint two coats over primer	192.5	sqm	129	24,832
22	Exterior weatherproof paint two coats	112.6	sqm	142	15,989
	TOTAL				1,794,154

Payment Schedule

Stage	Payment
Advance on agreement signing	15%
On completion of foundation	8%
On completion of plinth	5%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.