

SRI SAI CONSTRUCTIONS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. M. Farhan | Site: Gachibowli, Hyderabad | Built-up area: 1250 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Earthwork excavation in ordinary soil, foundation	64.7	cum	268	17,340
2	Refilling excavated soil around foundation	40.2	cum	146	5,869
3	Sand filling under floors, 100mm	12.7	cum	1,416	17,983
2. FOUNDATION & PLINTH					
4	Plain cement concrete 1:4:8 under footings	10.5	cum	6,000	63,000
5	Stone masonry foundation CM 1:6	25.5	cum	4,133	105,392
6	RCC M20 for plinth beam incl. shuttering	6.5	cum	7,863	51,110
7	DPC 50mm thick CC 1:2:4 over plinth	15.3	sqm	345	5,278
3. RCC SUPERSTRUCTURE					
8	M25 grade RCC — columns, beams, slab	31.7	cum	7,802	247,323
9	Reinforced concrete M25 staircase waist slab	3.8	cum	8,680	32,984
4. REINFORCEMENT					
10	TMT barsD, fabrication and placing	3204.6	kg	71	227,527
5. MASONRY					
11	Burnt clay brick masonry 230 mm in CM 1:6	32.1	cum	5,019	161,110
12	Brickwork in CM 1:4 for internal partitions, 115mm	53.5	sqm	771	41,248
6. PLASTERING					
13	Internal cement plaster 12mm in CM 1:4	218.6	sqm	168	36,725
7. FLOORING					
15	Vitrified tile flooring 600x600 incl. skirting	106.3	sqm	982	104,387
16	Wall tiles in bathrooms up to 7 feet	29.4	sqm	771	22,667
8. WATERPROOFING					
17	Waterproofing treatment to terrace and toilet sunk	68.7	sqm	615	42,250
9. ELECTRICAL					
18	Electrical points incl. conduit and wiring	53.6	pt	673	36,073
10. PLUMBING					
19	Concealed CPVC plumbing lines with fittings	5	set	10,101	50,505
11. ANTI-TERMITE					
20	Termite proofing to foundation trenches	70.5	sqm	2,227	157,004
12. PAINTING					
21	Interior emulsion paint two coats over primer	240	sqm	133	31,920
22	Exterior weatherproof paint two coats	131.1	sqm	152	19,927
	TOTAL				1,477,622

Payment Schedule

Stage	Payment
Advance on agreement signing	30%
On completion of foundation	15%
On completion of plinth	10%
On casting of roof slab	19%
On completion of brickwork & roof	16%
On finishing & handover	10%

Terms: Rates valid 30 days. Owner to provide water and electricity.