

PRAGATI BUILDCON

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. K. Srinivas | Site: Uppal, Hyderabad | Built-up area: 2000 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Digging of foundation trenches, ordinary soil	96.6	cum	261	25,213
2	Backfilling with excavated earth, watered and rammed	60.5	cum	143	8,652
3	Filling river sand below flooring 100 mm	20.1	cum	1,420	28,542
2. FOUNDATION & PLINTH					
4	Lean concrete bed below foundation	16	cum	5,754	92,064
5	Stone masonry foundation CM 1:6	42	cum	3,786	159,012
6	Reinforced cement concrete M20 plinth beam	9.7	cum	7,938	76,999
7	Damp proof course 50 mm, CC 1:2:4	23.4	sqm	310	7,254
3. RCC SUPERSTRUCTURE					
8	Reinforced cement concrete M25 for slab and beams	56.7	cum	8,428	477,868
9	Stair case RCC M25 incl. steps	6	cum	7,829	46,974
4. REINFORCEMENT					
10	Steel reinforcement TMT incl. binding	5403.1	kg	69	372,814
5. MASONRY					
11	External brick wall 9 inch, cement mortar 1:6	45.2	cum	5,214	235,673
12	Internal brick partition 4.5 inch	78.4	sqm	769	60,290
6. PLASTERING					
13	Inside wall plaster 12mm	370.3	sqm	180	66,654
14	External cement plaster 18mm in CM 1:4, two coats	208.4	sqm	231	48,140
7. FLOORING					
15	Floor tiling with vitrified tiles incl. skirting	172.2	sqm	1,125	193,725
16	Wall tiles in bathrooms up to 7 feet	47.2	sqm	814	38,421
8. WATERPROOFING					
17	Terrace and sunk waterproofing treatment	111	sqm	599	66,489
9. ELECTRICAL					
18	Concealed electrical wiring with copper conductor per point	87.6	pt	683	59,831
10. PLUMBING					
19	Concealed CPVC plumbing lines with fittings	7.4	set	11,601	85,847
11. ANTI-TERMITE					
20	Pre-construction anti termite treatment	107	sqm	2,142	229,194
12. PAINTING					
21	Interior painting, emulsion, over putty	373.5	sqm	127	47,434
22	Exterior emulsion weather coat, two coats	202.7	sqm	163	33,040
	TOTAL				2,460,130

Payment Schedule

Stage	Payment
Advance on agreement signing	30%
On completion of foundation	15%
On completion of plinth	10%
On casting of roof slab	19%
On completion of brickwork & roof	16%
On finishing & handover	10%

Terms: Rates valid 30 days. Owner to provide water and electricity.