

AKSHAYA HOMES

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. V. Naidu | Site: Shamirpet, Hyderabad | Built-up area: 2450 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Excavation for foundation in ordinary soil incl. disposal	120.8	cum	265	32,012
2	Backfilling with excavated earth, watered and rammed	77.9	cum	151	11,763
3	Sand bed under floor slab	25	cum	1,390	34,750
2. FOUNDATION & PLINTH					
4	Lean concrete bed below foundation	19.1	cum	5,706	108,985
5	Stone masonry foundation CM 1:6	51.2	cum	3,768	192,922
6	RCC M20 for plinth beam incl. shuttering	12.5	cum	7,798	97,475
7	DPC 50mm thick CC 1:2:4 over plinth	29.4	sqm	342	10,055
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	65.5	cum	7,833	513,062
9	Stair case RCC M25 incl. steps	6.9	cum	8,084	55,780
4. REINFORCEMENT					
10	Steel reinforcement TMT Fe 500 incl. binding	6315.4	kg	83	524,178
5. MASONRY					
11	External brick wall 9 inch, cement mortar 1:6	61.4	cum	5,192	318,789
12	Brickwork in CM 1:4 for internal partitions, 115mm	100.3	sqm	744	74,623
6. PLASTERING					
13	Inside wall plaster 12mm	415.1	sqm	183	75,963
7. FLOORING					
15	Vitrified tiles 2x2 ft laid on cement bed	211.9	sqm	1,021	216,350
16	Wall tiles in bathrooms up to 7 feet	57.6	sqm	776	44,698
8. WATERPROOFING					
17	Waterproofing treatment to terrace and toilet sunk	136.6	sqm	628	85,785
9. ELECTRICAL					
18	Internal concealed wiring, copper, per point	101.9	pt	664	67,662
10. PLUMBING					
19	Water supply piping CPVC, concealed	9.1	set	10,116	92,056
11. ANTI-TERMITE					
20	Anti-termite treatment to foundation and plinth	142.4	sqm	2,999	427,058
12. PAINTING					
21	Two coats acrylic emulsion on inside walls	450.6	sqm	139	62,633
22	Outside weatherproof painting	246.8	sqm	140	34,552
	TOTAL				3,081,151

Payment Schedule

Stage	Payment
Advance on agreement signing	20%
On completion of foundation	20%
On completion of plinth	12%
On casting of roof slab	20%
On completion of brickwork & roof	17%
On finishing & handover	11%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.