

PRAGATI BUILDCON

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. S. Reddy | Site: Shamirpet, Hyderabad | Built-up area: 2200 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Digging of foundation trenches, ordinary soil	108.9	cum	264	28,750
2	Backfilling with excavated earth, watered and rammed	72.6	cum	148	10,745
3	Filling river sand below flooring 100 mm	21	cum	1,418	29,778
2. FOUNDATION & PLINTH					
4	PCC 1:4:8 with 40mm aggregate below footings	18.7	cum	5,841	109,227
5	Random rubble masonry in cement mortar 1:6	48.2	cum	4,150	200,030
6	RCC M20 for plinth beam incl. shuttering	11.2	cum	7,540	84,448
7	Damp proof course 50 mm, CC 1:2:4	28.4	sqm	328	9,315
3. RCC SUPERSTRUCTURE					
8	Reinforced cement concrete M25 for slab and beams	58.1	cum	9,482	550,904
9	RCC M25 for staircase and landing	6.1	cum	8,373	51,075
4. REINFORCEMENT					
10	Steel reinforcement TMT incl. binding	5853.4	kg	68	398,031
5. MASONRY					
11	Burnt clay brick masonry 230 mm in CM 1:6	55.7	cum	5,056	281,619
12	Brickwork in CM 1:4 for internal partitions, 115mm	93.8	sqm	684	64,159
6. PLASTERING					
13	Internal cement plaster 12mm in CM 1:4	396.9	sqm	187	74,220
14	External cement plaster 18mm in CM 1:4, two coats	204.8	sqm	243	49,766
7. FLOORING					
15	Vitrified tile flooring 600x600 incl. skirting	192.7	sqm	981	189,039
16	Wall tiles in bathrooms up to 7 feet	49.9	sqm	785	39,172
8. WATERPROOFING					
17	Waterproofing treatment to terrace and toilet sunk	114.1	sqm	598	68,232
9. ELECTRICAL					
18	Electrical points incl. conduit and wiring	96.5	pt	664	64,076
10. PLUMBING					
19	CPVC water supply lines concealed incl. fittings	8.1	set	11,655	94,406
11. ANTI-TERMITE					
20	Termite proofing to foundation trenches	127.6	sqm	1,208	154,141
12. PAINTING					
21	Interior emulsion paint two coats over primer	420.3	sqm	143	60,103
22	Outside weatherproof painting	231.6	sqm	145	33,582
	TOTAL				2,644,818

Payment Schedule

Stage	Payment
Advance on agreement signing	20%
On completion of foundation	20%
On completion of plinth	12%
On casting of roof slab	20%
On completion of brickwork & roof	17%
On finishing & handover	11%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.