

NAVYA INFRA

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. B. Yadav | Site: Shamirpet, Hyderabad | Built-up area: 1250 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Earthwork excavation in ordinary soil, foundation	66.5	cum	258	17,157
2	Refilling excavated soil around foundation	40.5	cum	146	5,913
3	Filling river sand below flooring 100 mm	12.3	cum	1,369	16,839
2. FOUNDATION & PLINTH					
4	Plain cement concrete 1:4:8 under footings	10.8	cum	5,252	56,722
5	Size stone masonry in CM 1:6 for foundation	24.3	cum	4,196	101,963
6	RCC M20 for plinth beam incl. shuttering	6.2	cum	8,316	51,559
7	DPC 50mm thick CC 1:2:4 over plinth	14.2	sqm	338	4,800
3. RCC SUPERSTRUCTURE					
8	M25 grade RCC — columns, beams, slab	31.5	cum	8,097	255,056
9	Reinforced concrete M25 staircase waist slab	3.7	cum	7,793	28,834
4. REINFORCEMENT					
10	TMT reinforcement bars Fe500, cut bent and placed	3490.2	kg	67	233,843
5. MASONRY					
11	Brickwork in CM 1:6 for external walls, 230mm	32	cum	5,126	164,032
12	Half brick partition wall 115 mm CM 1:4	53.7	sqm	675	36,248
6. PLASTERING					
13	12 mm thick internal plastering CM 1:4	211.6	sqm	170	35,972
14	Outside wall plaster 18mm two coats	117.7	sqm	238	28,013
7. FLOORING					
15	Floor tiling with vitrified tiles incl. skirting	119.9	sqm	1,136	136,206
16	Toilet dado ceramic tiling	26.5	sqm	817	21,650
8. WATERPROOFING					
17	Waterproofing treatment to terrace and toilet sunk	66.2	sqm	606	40,117
9. ELECTRICAL					
18	Concealed electrical wiring with copper conductor per point	59.3	pt	682	40,443
10. PLUMBING					
19	CPVC water supply lines concealed incl. fittings	4.7	set	10,239	48,123
11. ANTI-TERMITE					
20	Termite proofing to foundation trenches	73.4	sqm	6,353	466,310
12. PAINTING					
21	Two coats acrylic emulsion on inside walls	226.5	sqm	145	32,842
22	Outside weatherproof painting	127.6	sqm	148	18,885
	TOTAL				1,841,527

Payment Schedule

Stage	Payment
Advance on agreement signing	10%
On completion of foundation	10%
On completion of plinth	8%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.