

SRI SAI CONSTRUCTIONS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. B. Yadav | Site: Kukatpally, Hyderabad | Built-up area: 1400 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Digging of foundation trenches, ordinary soil	70.6	cum	251	17,721
2	Backfilling with excavated earth, watered and rammed	40.6	cum	142	5,765
3	Sand filling under floors, 100mm	13.8	cum	1,411	19,472
2. FOUNDATION & PLINTH					
4	Lean concrete bed below foundation	10.3	cum	5,787	59,606
5	Size stone masonry in CM 1:6 for foundation	31.7	cum	4,022	127,497
6	Reinforced cement concrete M20 plinth beam	6.5	cum	7,928	51,532
7	Damp proof course 50 mm, CC 1:2:4	16.7	sqm	320	5,344
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	34.9	cum	7,673	267,788
9	Reinforced concrete M25 staircase waist slab	4.2	cum	8,644	36,305
4. REINFORCEMENT					
10	TMT barsD, fabrication and placing	3500.1	kg	71	248,507
5. MASONRY					
11	Burnt clay brick masonry 230 mm in CM 1:6	35.4	cum	5,207	184,328
12	Brickwork in CM 1:4 for internal partitions, 115mm	58.9	sqm	781	46,001
6. PLASTERING					
13	Inside wall plaster 12mm	249.1	sqm	182	45,336
14	18 mm external plastering, sponge finish	138.5	sqm	227	31,440
7. FLOORING					
15	Vitrified tiles 2x2 ft laid on cement bed	126.1	sqm	1,134	142,997
16	Toilet dado ceramic tiling	28.7	sqm	771	22,128
8. WATERPROOFING					
17	APP membrane waterproofing to terrace slab	83.2	sqm	584	48,589
9. ELECTRICAL					
18	Electrical points incl. conduit and wiring	60.7	pt	616	37,391
11. ANTI-TERMITE					
20	Anti-termite treatment to foundation and plinth	82.1	sqm	3,207	263,295
12. PAINTING					
21	Two coats acrylic emulsion on inside walls	253.5	sqm	128	32,448
22	Exterior weatherproof paint two coats	140.9	sqm	143	20,149
	TOTAL				1,713,639

Payment Schedule

Stage	Payment
Advance on agreement signing	20%
On completion of foundation	20%
On completion of plinth	12%
On casting of roof slab	20%
On completion of brickwork & roof	17%
On finishing & handover	11%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.