

NAVYA INFRA

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. B. Yadav | Site: Gachibowli, Hyderabad | Built-up area: 1400 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Excavation for foundation in ordinary soil incl. disposal	75	cum	256	19,200
2	Back filling and ramming in layers	40.4	cum	155	6,262
3	Filling river sand below flooring 100 mm	13.4	cum	1,267	16,978
2. FOUNDATION & PLINTH					
4	Plain cement concrete 1:4:8 under footings	11.2	cum	5,457	61,118
5	Stone masonry foundation CM 1:6	28.8	cum	3,799	109,411
6	Reinforced cement concrete M20 plinth beam	7.2	cum	8,320	59,904
7	DPC 50mm thick CC 1:2:4 over plinth	15.9	sqm	327	5,199
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	36.7	cum	8,686	318,776
9	Stair case RCC M25 incl. steps	4	cum	8,624	34,496
4. REINFORCEMENT					
10	Steel reinforcement TMT incl. binding	3644	kg	71	258,724
5. MASONRY					
11	External brick wall 9 inch, cement mortar 1:6	31.5	cum	5,506	173,439
12	Brickwork in CM 1:4 for internal partitions, 115mm	57.6	sqm	730	42,048
6. PLASTERING					
13	Internal cement plaster 12mm in CM 1:4	237.4	sqm	171	40,595
14	Outside wall plaster 18mm two coats	141.7	sqm	259	36,700
7. FLOORING					
15	Vitrified tiles 2x2 ft laid on cement bed	126.1	sqm	1,109	139,845
16	Toilet dado ceramic tiling	31.5	sqm	812	25,578
8. WATERPROOFING					
17	APP membrane waterproofing to terrace slab	74.8	sqm	594	44,431
9. ELECTRICAL					
18	Concealed electrical wiring with copper conductor per point	61.6	pt	623	38,377
10. PLUMBING					
19	Water supply piping CPVC, concealed	5.3	set	10,411	55,178
11. ANTI-TERMITE					
20	Anti-termite treatment to foundation and plinth	78.3	sqm	6,213	486,478
12. PAINTING					
21	Two coats acrylic emulsion on inside walls	230	sqm	126	28,980
22	Exterior emulsion weather coat, two coats	135.2	sqm	144	19,469
	TOTAL				2,021,186

Payment Schedule

Stage	Payment
Advance on agreement signing	10%
On completion of foundation	10%
On completion of plinth	8%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days. Owner to provide water and electricity.