

AKSHAYA HOMES

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. V. Naidu | Site: Uppal, Hyderabad | Built-up area: 2450 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Earthwork excavation in ordinary soil, foundation	115	cum	272	31,280
2	Refilling excavated soil around foundation	74.1	cum	140	10,374
3	Filling river sand below flooring 100 mm	24.2	cum	1,270	30,734
2. FOUNDATION & PLINTH					
4	Lean concrete bed below foundation	18.9	cum	6,062	114,572
5	Stone masonry foundation CM 1:6	51.5	cum	3,828	197,142
6	Plinth beam concrete M20 with formwork	12.6	cum	7,606	95,836
7	Damp proof course 50 mm, CC 1:2:4	28.5	sqm	321	9,148
3. RCC SUPERSTRUCTURE					
8	Reinforced cement concrete M25 for slab and beams	68.8	cum	8,078	555,766
9	Stair case RCC M25 incl. steps	7	cum	8,851	61,957
4. REINFORCEMENT					
10	Steel reinforcement TMT Fe 500 incl. binding	6913.6	kg	76	525,434
5. MASONRY					
11	External brick wall 9 inch, cement mortar 1:6	59.1	cum	5,651	333,974
12	Half brick partition wall 115 mm CM 1:4	99.1	sqm	717	71,055
6. PLASTERING					
13	12 mm thick internal plastering CM 1:4	445.3	sqm	191	85,052
14	External cement plaster 18mm in CM 1:4, two coats	259.5	sqm	293	76,034
7. FLOORING					
15	Floor tiling with vitrified tiles incl. skirting	230.8	sqm	1,040	240,032
16	Toilet dado ceramic tiling	54.3	sqm	792	43,006
8. WATERPROOFING					
17	APP membrane waterproofing to terrace slab	129.4	sqm	619	80,099
9. ELECTRICAL					
18	Internal concealed wiring, copper, per point	112.6	pt	642	72,289
10. PLUMBING					
19	Concealed CPVC plumbing lines with fittings	10.2	set	11,719	119,534
11. ANTI-TERMITE					
20	Anti-termite treatment to foundation and plinth	128.8	sqm	3,117	401,470
12. PAINTING					
21	Two coats acrylic emulsion on inside walls	426.8	sqm	140	59,752
22	Exterior weatherproof paint two coats	255.6	sqm	147	37,573
	TOTAL				3,252,113

Payment Schedule

Stage	Payment
Advance on agreement signing	20%
On completion of foundation	20%
On completion of plinth	12%
On casting of roof slab	20%
On completion of brickwork & roof	17%
On finishing & handover	11%

Terms: Rates valid 30 days. Owner to provide water and electricity.