

VENKATESHWARA BUILDERS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. V. Naidu | Site: Shamirpet, Hyderabad | Built-up area: 1100 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Digging of foundation trenches, ordinary soil	52.5	cum	255	13,388
2	Back filling and ramming in layers	35.8	cum	140	5,012
3	Sand filling under floors, 100mm	11.4	cum	1,444	16,462
2. FOUNDATION & PLINTH					
4	Plain cement concrete 1:4:8 under footings	8.2	cum	5,347	43,845
5	Random rubble masonry in cement mortar 1:6	22.9	cum	4,056	92,882
6	Reinforced cement concrete M20 plinth beam	5.6	cum	8,636	48,362
7	DPC 50mm thick CC 1:2:4 over plinth	12.2	sqm	302	3,684
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	27.8	cum	8,360	232,408
9	RCC M25 for staircase and landing	3.2	cum	7,956	25,459
4. REINFORCEMENT					
10	TMT bars, cut bent and placed	2773.9	kg	69	191,399
5. MASONRY					
11	Brickwork in CM 1:6 for external walls, 230mm	27.9	cum	5,006	139,667
12	Internal brick partition 4.5 inch	41.3	sqm	748	30,892
6. PLASTERING					
13	Inside wall plaster 12mm	180.9	sqm	195	35,276
14	External cement plaster 18mm in CM 1:4, two coats	118.3	sqm	224	26,499
7. FLOORING					
15	Vitrified tile flooring 600x600 incl. skirting	101.8	sqm	1,116	113,609
16	Wall tiles in bathrooms up to 7 feet	23.6	sqm	878	20,721
8. WATERPROOFING					
17	Waterproofing treatment to terrace and toilet sunk	62.1	sqm	656	40,738
9. ELECTRICAL					
18	Internal concealed wiring, copper, per point	45	pt	621	27,945
10. PLUMBING					
19	Concealed CPVC plumbing lines with fittings	4.7	set	11,300	53,110
11. ANTI-TERMITE					
20	Pre-construction anti termite treatment	58.5	sqm	2,086	122,031
12. PAINTING					
21	Interior painting, emulsion, over putty	181.2	sqm	139	25,187
22	Outside weatherproof painting	107	sqm	160	17,120
	TOTAL				1,325,696

Payment Schedule

Stage	Payment
Advance on agreement signing	30%
On completion of foundation	15%
On completion of plinth	10%
On casting of roof slab	19%
On completion of brickwork & roof	16%
On finishing & handover	10%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.