

PRAGATI BUILDCON

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mrs. T. Lakshmi | Site: Uppal, Hyderabad | Built-up area: 1650 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Excavation for foundation in ordinary soil incl. disposal	80.2	cum	273	21,895
2	Back filling and ramming in layers	52.6	cum	141	7,417
3	Filling river sand below flooring 100 mm	16.4	cum	1,333	21,861
2. FOUNDATION & PLINTH					
4	Lean concrete bed below foundation	12.8	cum	5,270	67,456
5	Size stone masonry in CM 1:6 for foundation	33.8	cum	4,139	139,898
6	Plinth beam concrete M20 with formwork	8.5	cum	8,439	71,732
7	DPC 50mm thick CC 1:2:4 over plinth	18.6	sqm	324	6,026
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	45.2	cum	8,474	383,025
9	RCC M25 for staircase and landing	4.8	cum	8,453	40,574
4. REINFORCEMENT					
10	Steel reinforcement TMT Fe 500 incl. binding	4513.9	kg	69	311,459
5. MASONRY					
11	Brickwork in CM 1:6 for external walls, 230mm	40.6	cum	5,574	226,304
12	Internal brick partition 4.5 inch	68.1	sqm	690	46,989
6. PLASTERING					
13	Inside wall plaster 12mm	316.6	sqm	168	53,189
14	18 mm external plastering, sponge finish	174.6	sqm	223	38,936
7. FLOORING					
15	Vitrified tile flooring 600x600 incl. skirting	152.6	sqm	1,031	157,331
16	Toilet dado ceramic tiling	37.8	sqm	886	33,491
8. WATERPROOFING					
17	Waterproofing treatment to terrace and toilet sunk	98.1	sqm	672	65,923
9. ELECTRICAL					
18	Internal concealed wiring, copper, per point	73.4	pt	617	45,288
10. PLUMBING					
19	Concealed CPVC plumbing lines with fittings	6.6	set	11,374	75,068
11. ANTI-TERMITE					
20	Anti-termite treatment to foundation and plinth	97.9	sqm	381	37,300
12. PAINTING					
21	Interior emulsion paint two coats over primer	279.3	sqm	129	36,030
22	Exterior emulsion weather coat, two coats	170.7	sqm	154	26,288
	TOTAL				1,913,480

Payment Schedule

Stage	Payment
Advance on agreement signing	15%
On completion of foundation	8%
On completion of plinth	5%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.