

AKSHAYA HOMES

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. M. Farhan | Site: Kompally, Hyderabad | Built-up area: 1100 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Digging of foundation trenches, ordinary soil	54	cum	258	13,932
2	Refilling excavated soil around foundation	33.8	cum	144	4,867
3	Sand bed under floor slab	11.4	cum	1,280	14,592
2. FOUNDATION & PLINTH					
4	Plain cement concrete 1:4:8 under footings	9	cum	5,472	49,248
5	Size stone masonry in CM 1:6 for foundation	23.9	cum	4,181	99,926
6	Reinforced cement concrete M20 plinth beam	5.1	cum	7,488	38,189
7	DPC layer above plinth level	13.5	sqm	328	4,428
3. RCC SUPERSTRUCTURE					
8	Reinforced cement concrete M25 for slab and beams	31.5	cum	7,696	242,424
9	Reinforced concrete M25 staircase waist slab	3.1	cum	7,847	24,326
4. REINFORCEMENT					
10	Steel reinforcement TMT incl. binding	2789.1	kg	75	209,182
5. MASONRY					
11	External brick wall 9 inch, cement mortar 1:6	25.6	cum	5,212	133,427
12	Brickwork in CM 1:4 for internal partitions, 115mm	43.2	sqm	725	31,320
6. PLASTERING					
13	Internal cement plaster 12mm in CM 1:4	200.8	sqm	178	35,742
14	Outside wall plaster 18mm two coats	114.2	sqm	234	26,723
7. FLOORING					
15	Vitrified tile flooring 600x600 incl. skirting	95.8	sqm	1,067	102,219
16	Toilet dado ceramic tiling	26.1	sqm	768	20,045
8. WATERPROOFING					
17	Terrace and sunk waterproofing treatment	57.7	sqm	591	34,101
9. ELECTRICAL					
18	Internal concealed wiring, copper, per point	47.9	pt	623	29,842
10. PLUMBING					
19	Water supply piping CPVC, concealed	4.6	set	10,143	46,658
11. ANTI-TERMITE					
20	Termite proofing to foundation trenches	61.9	sqm	2,500	154,750
12. PAINTING					
21	Two coats acrylic emulsion on inside walls	208.3	sqm	133	27,704
22	Exterior emulsion weather coat, two coats	105.2	sqm	156	16,411
	TOTAL				1,360,056

Payment Schedule

Stage	Payment
Advance on agreement signing	25%
On completion of foundation	15%
On completion of plinth	10%
On casting of roof slab	21%
On completion of brickwork & roof	18%
On finishing & handover	11%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.