

SRI SAI CONSTRUCTIONS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mrs. P. Anjali | Site: Kukatpally, Hyderabad | Built-up area: 1100 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Excavation for foundation in ordinary soil incl. disposal	56.5	cum	271	15,312
2	Refilling excavated soil around foundation	32.6	cum	153	4,988
3	Sand bed under floor slab	10.8	cum	1,394	15,055
2. FOUNDATION & PLINTH					
4	PCC 1:4:8 with 40mm aggregate below footings	8.8	cum	5,665	49,852
5	Stone masonry foundation CM 1:6	23.4	cum	4,090	95,706
6	Plinth beam concrete M20 with formwork	5.3	cum	8,422	44,637
7	Damp proof course 50 mm, CC 1:2:4	13.6	sqm	317	4,311
3. RCC SUPERSTRUCTURE					
8	M25 grade RCC — columns, beams, slab	27.7	cum	8,239	228,220
9	Stair case RCC M25 incl. steps	3.1	cum	8,249	25,572
4. REINFORCEMENT					
10	TMT bars Fe500D, fabrication and placing	2968.1	kg	65	192,926
5. MASONRY					
11	External brick wall 9 inch, cement mortar 1:6	25.9	cum	5,340	138,306
12	Half brick partition wall 115 mm CM 1:4	43.7	sqm	781	34,130
6. PLASTERING					
13	Inside wall plaster 12mm	183.4	sqm	172	31,545
14	External cement plaster 18mm in CM 1:4, two coats	113.2	sqm	235	26,602
7. FLOORING					
15	Vitrified tiles 2x2 ft laid on cement bed	98.6	sqm	1,002	98,797
16	Wall tiles in bathrooms up to 7 feet	26	sqm	804	20,904
8. WATERPROOFING					
17	Terrace and sunk waterproofing treatment	60.4	sqm	664	40,106
9. ELECTRICAL					
18	Electrical points incl. conduit and wiring	49.1	pt	706	34,665
10. PLUMBING					
19	Water supply piping CPVC, concealed	4.6	set	10,123	46,566
11. ANTI-TERMITE					
20	Anti-termite treatment to foundation and plinth	65.1	sqm	8,515	554,326
12. PAINTING					
21	Interior painting, emulsion, over putty	184.7	sqm	128	23,642
22	Outside weatherproof painting	110.8	sqm	151	16,731
	TOTAL				1,742,899

Payment Schedule

Stage	Payment
Advance on agreement signing	10%
On completion of foundation	12%
On completion of plinth	6%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.