

SRI SAI CONSTRUCTIONS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mrs. P. Anjali | Site: Kukatpally, Hyderabad | Built-up area: 2450 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Earthwork excavation in ordinary soil, foundation	125.9	cum	269	33,867
2	Backfilling with excavated earth, watered and rammed	70.2	cum	147	10,319
3	Sand bed under floor slab	25	cum	1,274	31,850
2. FOUNDATION & PLINTH					
4	PCC 1:4:8 with 40mm aggregate below footings	19.8	cum	5,277	104,485
5	Size stone masonry in CM 1:6 for foundation	55.3	cum	4,340	240,002
6	RCC M20 for plinth beam incl. shuttering	12.7	cum	7,926	100,660
7	Damp proof course 50 mm, CC 1:2:4	28.1	sqm	325	9,132
3. RCC SUPERSTRUCTURE					
8	M25 grade RCC — columns, beams, slab	68.1	cum	7,859	535,198
9	Reinforced concrete M25 staircase waist slab	7.2	cum	8,248	59,386
4. REINFORCEMENT					
10	TMT bars, cut bent and placed	6605.3	kg	74	488,792
5. MASONRY					
11	Brickwork in CM 1:6 for external walls, 230mm	56.6	cum	5,561	314,753
12	Internal brick partition 4.5 inch	91.6	sqm	719	65,860
6. PLASTERING					
13	Inside wall plaster 12mm	420.2	sqm	181	76,056
14	External cement plaster 18mm in CM 1:4, two coats	249.4	sqm	241	60,105
7. FLOORING					
15	Vitrified tile flooring 600x600 incl. skirting	213.4	sqm	1,239	264,403
16	Ceramic tile dado in toilets up to 7ft	57.3	sqm	815	46,700
8. WATERPROOFING					
17	Waterproofing treatment to terrace and toilet sunk	132.1	sqm	607	80,185
9. ELECTRICAL					
18	Internal concealed wiring, copper, per point	109	pt	636	69,324
10. PLUMBING					
19	CPVC water supply lines concealed incl. fittings	9.4	set	10,813	101,642
11. ANTI-TERMITE					
20	Anti-termite treatment to foundation and plinth	137.7	sqm	1,704	234,641
12. PAINTING					
21	Interior emulsion paint two coats over primer	452.1	sqm	135	61,034
22	Outside weatherproof painting	254.6	sqm	141	35,899
	TOTAL				3,024,293

Payment Schedule

Stage	Payment
Advance on agreement signing	20%
On completion of foundation	20%
On completion of plinth	12%
On casting of roof slab	20%
On completion of brickwork & roof	17%
On finishing & handover	11%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.