

SRI SAI CONSTRUCTIONS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. S. Reddy | Site: Uppal, Hyderabad | Built-up area: 1800 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Digging of foundation trenches, ordinary soil	98.3	cum	255	25,066
2	Refilling excavated soil around foundation	59.2	cum	138	8,170
3	Filling river sand below flooring 100 mm	17.6	cum	1,464	25,766
2. FOUNDATION & PLINTH					
4	PCC 1:4:8 with 40mm aggregate below footings	13.9	cum	5,453	75,797
5	Stone masonry foundation CM 1:6	38	cum	3,928	149,264
6	Reinforced cement concrete M20 plinth beam	9.7	cum	8,747	84,846
7	Damp proof course 50 mm, CC 1:2:4	20.6	sqm	333	6,860
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	51.7	cum	7,481	386,768
9	RCC M25 for staircase and landing	5	cum	7,760	38,800
4. REINFORCEMENT					
10	TMT barsD, fabrication and placing	4825.7	kg	71	342,625
5. MASONRY					
11	Brickwork in CM 1:6 for external walls, 230mm	41.2	cum	5,408	222,810
12	Brickwork in CM 1:4 for internal partitions, 115mm	77.7	sqm	700	54,390
6. PLASTERING					
13	Internal cement plaster 12mm in CM 1:4	339	sqm	196	66,444
14	Outside wall plaster 18mm two coats	189.7	sqm	248	47,046
7. FLOORING					
15	Vitrified tile flooring 600x600 incl. skirting	170.5	sqm	1,119	190,790
16	Wall tiles in bathrooms up to 7 feet	36.8	sqm	763	28,078
9. ELECTRICAL					
18	Concealed electrical wiring with copper conductor per point	73.2	pt	670	49,044
10. PLUMBING					
19	CPVC water supply lines concealed incl. fittings	7.3	set	10,420	76,066
11. ANTI-TERMITE					
20	Termite proofing to foundation trenches	103.7	sqm	8,053	835,096
12. PAINTING					
21	Interior emulsion paint two coats over primer	297.5	sqm	137	40,758
22	Exterior emulsion weather coat, two coats	192.1	sqm	145	27,854
	TOTAL				2,782,338

Payment Schedule

Stage	Payment
Advance on agreement signing	10%
On completion of foundation	12%
On completion of plinth	6%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days. Owner to provide water and electricity.