

PRAGATI BUILDCON

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. S. Reddy | Site: Gachibowli, Hyderabad | Built-up area: 1100 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Earthwork excavation in ordinary soil, foundation	60.1	cum	255	15,326
2	Refilling excavated soil around foundation	35.5	cum	142	5,041
3	Sand filling under floors, 100mm	11.5	cum	1,257	14,456
2. FOUNDATION & PLINTH					
4	Lean concrete bed below foundation	8.3	cum	5,219	43,318
5	Random rubble masonry in cement mortar 1:6	24.4	cum	4,212	102,773
6	Reinforced cement concrete M20 plinth beam	5.7	cum	8,027	45,754
7	DPC layer above plinth level	12.9	sqm	344	4,438
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	27.5	cum	7,638	210,045
9	Reinforced concrete M25 staircase waist slab	3.2	cum	8,138	26,042
4. REINFORCEMENT					
10	Steel reinforcement TMT Fe 500 incl. binding	2880.3	kg	74	213,142
5. MASONRY					
11	External brick wall 9 inch, cement mortar 1:6	28.4	cum	5,569	158,160
12	Brickwork in CM 1:4 for internal partitions, 115mm	45.8	sqm	698	31,968
6. PLASTERING					
13	12 mm thick internal plastering CM 1:4	182.8	sqm	185	33,818
14	External cement plaster 18mm in CM 1:4, two coats	102	sqm	235	23,970
7. FLOORING					
15	Vitrified tile flooring 600x600 incl. skirting	96.6	sqm	1,087	105,004
16	Wall tiles in bathrooms up to 7 feet	23.6	sqm	837	19,753
8. WATERPROOFING					
17	Terrace and sunk waterproofing treatment	61.3	sqm	615	37,700
10. PLUMBING					
19	Water supply piping CPVC, concealed	4.1	set	10,073	41,299
11. ANTI-TERMITE					
20	Termite proofing to foundation trenches	59	sqm	670	39,530
12. PAINTING					
21	Interior emulsion paint two coats over primer	194.8	sqm	143	27,856
22	Outside weatherproof painting	107.3	sqm	157	16,846
	TOTAL				1,216,239

Payment Schedule

Stage	Payment
Advance on agreement signing	10%
On completion of foundation	12%
On completion of plinth	6%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days. Owner to provide water and electricity.