

SRINIVASA CONSTRUCTIONS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mrs. T. Lakshmi | Site: Miyapur, Hyderabad | Built-up area: 1100 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Earthwork excavation in ordinary soil, foundation	54.5	cum	269	14,660
2	Refilling excavated soil around foundation	34.8	cum	153	5,324
3	Filling river sand below flooring 100 mm	11.5	cum	1,354	15,571
2. FOUNDATION & PLINTH					
4	PCC 1:4:8 with 40mm aggregate below footings	8.8	cum	6,027	53,038
5	Size stone masonry in CM 1:6 for foundation	24.8	cum	3,837	95,158
6	Plinth beam concrete M20 with formwork	5.8	cum	8,220	47,676
7	DPC layer above plinth level	13.6	sqm	336	4,570
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	30.6	cum	8,259	252,725
9	RCC M25 for staircase and landing	3.3	cum	8,254	27,238
4. REINFORCEMENT					
10	TMT bars Fe500D, fabrication and placing	2964.1	kg	70	207,487
5. MASONRY					
11	External brick wall 9 inch, cement mortar 1:6	26.8	cum	5,070	135,876
12	Internal brick partition 4.5 inch	43	sqm	777	33,411
6. PLASTERING					
13	12 mm thick internal plastering CM 1:4	194.9	sqm	192	37,421
14	External cement plaster 18mm in CM 1:4, two coats	109.4	sqm	228	24,943
7. FLOORING					
15	Vitrified tiles 2x2 ft laid on cement bed	97.7	sqm	1,118	109,229
16	Ceramic tile dado in toilets up to 7ft	23.5	sqm	867	20,374
8. WATERPROOFING					
17	Waterproofing treatment to terrace and toilet sunk	65.9	sqm	596	39,276
9. ELECTRICAL					
18	Internal concealed wiring, copper, per point	50.2	pt	643	32,279
10. PLUMBING					
19	Water supply piping CPVC, concealed	4.5	set	10,867	48,902
11. ANTI-TERMITE					
20	Anti-termite treatment to foundation and plinth	65	sqm	8,963	582,595
12. PAINTING					
21	Interior emulsion paint two coats over primer	187.8	sqm	134	25,165
22	Exterior emulsion weather coat, two coats	118.1	sqm	147	17,361
	TOTAL				1,830,279

Payment Schedule

Stage	Payment
Advance on agreement signing	15%
On completion of foundation	8%
On completion of plinth	5%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.