

NAVYA INFRA

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mrs. G. Swathi | Site: Medchal, Hyderabad | Built-up area: 2200 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Excavation for foundation in ordinary soil incl. disposal	111.5	cum	263	29,324
2	Backfilling with excavated earth, watered and rammed	72.4	cum	132	9,557
3	Filling river sand below flooring 100 mm	21.6	cum	1,284	27,734
2. FOUNDATION & PLINTH					
4	Plain cement concrete 1:4:8 under footings	16.9	cum	5,673	95,874
5	Stone masonry foundation CM 1:6	49	cum	4,086	200,214
6	Reinforced cement concrete M20 plinth beam	10.6	cum	7,797	82,648
7	Damp proof course 50 mm, CC 1:2:4	24.5	sqm	340	8,330
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	56.8	cum	8,178	464,510
9	RCC M25 for staircase and landing	7.1	cum	7,616	54,074
4. REINFORCEMENT					
10	Steel reinforcement TMT Fe 500 incl. binding	5942.9	kg	74	439,775
5. MASONRY					
11	External brick wall 9 inch, cement mortar 1:6	51	cum	6,254	318,954
12	Half brick partition wall 115 mm CM 1:4	88.1	sqm	775	68,278
6. PLASTERING					
13	12 mm thick internal plastering CM 1:4	363.5	sqm	186	67,611
14	External cement plaster 18mm in CM 1:4, two coats	215.3	sqm	261	56,193
7. FLOORING					
15	Vitrified tiles 2x2 ft laid on cement bed	197.4	sqm	1,011	199,571
16	Toilet dado ceramic tiling	45.3	sqm	834	37,780
8. WATERPROOFING					
17	APP membrane waterproofing to terrace slab	120.1	sqm	672	80,707
9. ELECTRICAL					
18	Electrical points incl. conduit and wiring	95.6	pt	680	65,008
10. PLUMBING					
19	CPVC water supply lines concealed incl. fittings	9.3	set	10,884	101,221
11. ANTI-TERMITE					
20	Pre-construction anti termite treatment	119.7	sqm	7,299	873,690
12. PAINTING					
21	Interior emulsion paint two coats over primer	418.7	sqm	134	56,106
22	Exterior weatherproof paint two coats	235.5	sqm	141	33,206
	TOTAL				3,370,365

Payment Schedule

Stage	Payment
Advance on agreement signing	25%
On completion of foundation	15%
On completion of plinth	10%
On casting of roof slab	21%
On completion of brickwork & roof	18%
On finishing & handover	11%

Terms: Rates valid 30 days. Owner to provide water and electricity.