

SRI SAI CONSTRUCTIONS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. M. Farhan | Site: Nizampet, Hyderabad | Built-up area: 1650 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Excavation for foundation in ordinary soil incl. disposal	86.3	cum	261	22,524
2	Backfilling with excavated earth, watered and rammed	50.2	cum	141	7,078
3	Sand filling under floors, 100mm	15.4	cum	1,289	19,851
2. FOUNDATION & PLINTH					
4	Plain cement concrete 1:4:8 under footings	12.3	cum	5,637	69,335
5	Size stone masonry in CM 1:6 for foundation	35.4	cum	4,092	144,857
6	Plinth beam concrete M20 with formwork	7.6	cum	7,977	60,625
7	Damp proof course 50 mm, CC 1:2:4	19.2	sqm	314	6,029
3. RCC SUPERSTRUCTURE					
8	Reinforced cement concrete M25 for slab and beams	44.9	cum	8,067	362,208
9	Reinforced concrete M25 staircase waist slab	5.3	cum	7,677	40,688
4. REINFORCEMENT					
10	TMT bars, cut bent and placed	4242.6	kg	73	309,710
5. MASONRY					
11	External brick wall 9 inch, cement mortar 1:6	38.7	cum	5,220	202,014
12	Half brick partition wall 115 mm CM 1:4	67.3	sqm	677	45,562
6. PLASTERING					
13	Inside wall plaster 12mm	287.8	sqm	183	52,667
14	External cement plaster 18mm in CM 1:4, two coats	161.2	sqm	246	39,655
7. FLOORING					
15	Vitrified tiles 2x2 ft laid on cement bed	151.9	sqm	1,063	161,470
16	Ceramic tile dado in toilets up to 7ft	34.4	sqm	840	28,896
8. WATERPROOFING					
17	APP membrane waterproofing to terrace slab	95	sqm	638	60,610
9. ELECTRICAL					
18	Internal concealed wiring, copper, per point	69.8	pt	671	46,836
10. PLUMBING					
19	Concealed CPVC plumbing lines with fittings	6.3	set	11,674	73,546
11. ANTI-TERMITE					
20	Termite proofing to foundation trenches	91.1	sqm	4,687	426,986
12. PAINTING					
21	Interior emulsion paint two coats over primer	283.2	sqm	143	40,498
22	Exterior weatherproof paint two coats	155.8	sqm	189	29,446
	TOTAL				2,251,091

Payment Schedule

Stage	Payment
Advance on agreement signing	25%
On completion of foundation	15%
On completion of plinth	10%
On casting of roof slab	21%
On completion of brickwork & roof	18%
On finishing & handover	11%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.