

LAKSHMI CONSTRUCTIONS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. K. Srinivas | Site: Medchal, Hyderabad | Built-up area: 1100 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Excavation for foundation in ordinary soil incl. disposal	53.7	cum	250	13,425
2	Backfilling with excavated earth, watered and rammed	32.4	cum	139	4,504
3	Sand filling under floors, 100mm	10.2	cum	1,378	14,056
2. FOUNDATION & PLINTH					
4	Lean concrete bed below foundation	8.4	cum	5,623	47,233
5	Size stone masonry in CM 1:6 for foundation	23.8	cum	3,861	91,892
6	Plinth beam concrete M20 with formwork	5.1	cum	8,605	43,886
7	DPC layer above plinth level	14	sqm	321	4,494
3. RCC SUPERSTRUCTURE					
8	M25 grade RCC — columns, beams, slab	29	cum	7,483	217,007
9	Stair case RCC M25 incl. steps	3.6	cum	7,903	28,451
4. REINFORCEMENT					
10	TMT reinforcement bars Fe500, cut bent and placed	2853.8	kg	65	185,497
5. MASONRY					
11	Brickwork in CM 1:6 for external walls, 230mm	26.9	cum	5,444	146,444
12	Brickwork in CM 1:4 for internal partitions, 115mm	44.6	sqm	747	33,316
6. PLASTERING					
13	12 mm thick internal plastering CM 1:4	199.5	sqm	247	49,276
14	18 mm external plastering, sponge finish	113.9	sqm	252	28,703
7. FLOORING					
15	Floor tiling with vitrified tiles incl. skirting	96.3	sqm	1,043	100,441
16	Toilet dado ceramic tiling	25.8	sqm	856	22,085
8. WATERPROOFING					
17	Waterproofing treatment to terrace and toilet sunk	62.6	sqm	619	38,749
9. ELECTRICAL					
18	Electrical points incl. conduit and wiring	46.1	pt	671	30,933
10. PLUMBING					
19	Concealed CPVC plumbing lines with fittings	4.7	set	11,681	54,901
11. ANTI-TERMITE					
20	Anti-termite treatment to foundation and plinth	57.8	sqm	6,545	378,301
12. PAINTING					
21	Two coats acrylic emulsion on inside walls	189.5	sqm	139	26,340
22	Outside weatherproof painting	115.9	sqm	141	16,342
	TOTAL				1,576,276

Payment Schedule

Stage	Payment
Advance on agreement signing	25%
On completion of foundation	15%
On completion of plinth	10%
On casting of roof slab	21%
On completion of brickwork & roof	18%
On finishing & handover	11%

Terms: Rates valid 30 days. Owner to provide water and electricity.