

SAI TEJA ENGINEERS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. M. Farhan | Site: Bachupally, Hyderabad | Built-up area: 2450 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Excavation for foundation in ordinary soil incl. disposal	116.4	cum	250	29,100
2	Back filling and ramming in layers	78.3	cum	138	10,805
3	Sand filling under floors, 100mm	23.9	cum	1,321	31,572
2. FOUNDATION & PLINTH					
4	Lean concrete bed below foundation	19.1	cum	5,803	110,837
5	Random rubble masonry in cement mortar 1:6	55.2	cum	3,968	219,034
6	RCC M20 for plinth beam incl. shuttering	11.6	cum	8,437	97,869
7	Damp proof course 50 mm, CC 1:2:4	27.2	sqm	308	8,378
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	69.9	cum	8,682	606,872
9	Stair case RCC M25 incl. steps	7.6	cum	8,010	60,876
4. REINFORCEMENT					
10	Steel reinforcement TMT incl. binding	6970.8	kg	71	494,927
5. MASONRY					
11	External brick wall 9 inch, cement mortar 1:6	57.9	cum	5,075	293,842
12	Half brick partition wall 115 mm CM 1:4	93.1	sqm	762	70,942
6. PLASTERING					
13	Internal cement plaster 12mm in CM 1:4	458.1	sqm	175	80,168
14	External cement plaster 18mm in CM 1:4, two coats	256.8	sqm	238	61,118
7. FLOORING					
15	Vitrified tiles 2x2 ft laid on cement bed	233	sqm	1,116	260,028
16	Ceramic tile dado in toilets up to 7ft	50.7	sqm	862	43,703
8. WATERPROOFING					
17	APP membrane waterproofing to terrace slab	130	sqm	596	77,480
9. ELECTRICAL					
18	Concealed electrical wiring with copper conductor per point	100.4	pt	715	71,786
10. PLUMBING					
19	Water supply piping CPVC, concealed	10.5	set	10,813	113,536
11. ANTI-TERMITE					
20	Pre-construction anti termite treatment	138	sqm	7,838	1,081,644
12. PAINTING					
21	Two coats acrylic emulsion on inside walls	449.4	sqm	138	62,017
22	Outside weatherproof painting	242.7	sqm	160	38,832
	TOTAL				3,925,366

Payment Schedule

Stage	Payment
Advance on agreement signing	10%
On completion of foundation	10%
On completion of plinth	8%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.