

NAVYA INFRA

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. S. Reddy | Site: Uppal, Hyderabad | Built-up area: 2200 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Earthwork excavation in ordinary soil, foundation	111.5	cum	234	26,091
2	Refilling excavated soil around foundation	69.5	cum	134	9,313
3	Sand bed under floor slab	21.2	cum	1,768	37,482
2. FOUNDATION & PLINTH					
4	Plain cement concrete 1:4:8 under footings	18.8	cum	5,325	100,110
5	Stone masonry foundation CM 1:6	46.8	cum	4,265	199,602
6	RCC M20 for plinth beam incl. shuttering	10.4	cum	8,380	87,152
7	DPC 50mm thick CC 1:2:4 over plinth	27.8	sqm	311	8,646
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	57.8	cum	7,508	433,962
9	RCC M25 for staircase and landing	6.4	cum	7,933	50,771
4. REINFORCEMENT					
10	Steel reinforcement TMT Fe 500 incl. binding	5699.1	kg	75	427,432
5. MASONRY					
11	External brick wall 9 inch, cement mortar 1:6	55.2	cum	5,745	317,124
12	Half brick partition wall 115 mm CM 1:4	94	sqm	679	63,826
6. PLASTERING					
13	12 mm thick internal plastering CM 1:4	382.2	sqm	189	72,236
14	Outside wall plaster 18mm two coats	203.7	sqm	247	50,314
7. FLOORING					
15	Vitrified tiles 2x2 ft laid on cement bed	184.3	sqm	1,030	189,829
16	Ceramic tile dado in toilets up to 7ft	46.2	sqm	783	36,175
8. WATERPROOFING					
17	Terrace and sunk waterproofing treatment	128.3	sqm	661	84,806
9. ELECTRICAL					
18	Internal concealed wiring, copper, per point	92.4	pt	648	59,875
10. PLUMBING					
19	CPVC water supply lines concealed incl. fittings	9.1	set	10,793	98,216
11. ANTI-TERMITE					
20	Anti-termite treatment to foundation and plinth	119.7	sqm	1,492	178,592
12. PAINTING					
21	Interior painting, emulsion, over putty	366.1	sqm	128	46,861
22	Outside weatherproof painting	218.3	sqm	156	34,055
	TOTAL				2,612,470

Payment Schedule

Stage	Payment
Advance on agreement signing	25%
On completion of foundation	15%
On completion of plinth	10%
On casting of roof slab	21%
On completion of brickwork & roof	18%
On finishing & handover	11%

Terms: Rates valid 30 days. Owner to provide water and electricity.