

PRAGATI BUILDCON

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. V. Naidu | Site: Uppal, Hyderabad | Built-up area: 1250 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Excavation for foundation in ordinary soil incl. disposal	62.2	cum	246	15,301
2	Backfilling with excavated earth, watered and rammed	39.5	cum	195	7,702
3	Sand filling under floors, 100mm	12.5	cum	1,397	17,462
2. FOUNDATION & PLINTH					
4	PCC 1:4:8 with 40mm aggregate below footings	10.1	cum	5,509	55,641
5	Random rubble masonry in cement mortar 1:6	27.2	cum	4,259	115,845
6	Reinforced cement concrete M20 plinth beam	6.7	cum	8,588	57,540
7	Damp proof course 50 mm, CC 1:2:4	15.6	sqm	343	5,351
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	31.9	cum	7,982	254,626
9	RCC M25 for staircase and landing	3.8	cum	8,763	33,299
4. REINFORCEMENT					
10	TMT reinforcement bars Fe500, cut bent and placed	3396	kg	70	237,720
5. MASONRY					
11	Burnt clay brick masonry 230 mm in CM 1:6	29.8	cum	5,776	172,125
12	Brickwork in CM 1:4 for internal partitions, 115mm	48.3	sqm	708	34,196
6. PLASTERING					
13	12 mm thick internal plastering CM 1:4	217.7	sqm	190	41,363
14	Outside wall plaster 18mm two coats	116.5	sqm	256	29,824
7. FLOORING					
15	Floor tiling with vitrified tiles incl. skirting	118	sqm	1,007	118,826
16	Ceramic tile dado in toilets up to 7ft	27.8	sqm	821	22,824
8. WATERPROOFING					
17	APP membrane waterproofing to terrace slab	75.3	sqm	636	47,891
9. ELECTRICAL					
18	Internal concealed wiring, copper, per point	57.2	pt	646	36,951
10. PLUMBING					
19	Water supply piping CPVC, concealed	4.7	set	11,157	52,438
11. ANTI-TERMITE					
20	Pre-construction anti termite treatment	67.5	sqm	6,813	459,878
12. PAINTING					
21	Interior emulsion paint two coats over primer	222.4	sqm	127	28,245
22	Outside weatherproof painting	124.4	sqm	155	19,282
	TOTAL				1,864,330

Payment Schedule

Stage	Payment
Advance on agreement signing	20%
On completion of foundation	20%
On completion of plinth	12%
On casting of roof slab	20%
On completion of brickwork & roof	17%
On finishing & handover	11%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.