

VENKATESHWARA BUILDERS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. B. Yadav | Site: Patancheru, Hyderabad | Built-up area: 1250 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Earthwork excavation in ordinary soil, foundation	60.2	cum	249	14,990
2	Backfilling with excavated earth, watered and rammed	38.5	cum	143	5,506
3	Sand filling under floors, 100mm	11.6	cum	1,387	16,089
2. FOUNDATION & PLINTH					
4	Plain cement concrete 1:4:8 under footings	9.6	cum	5,290	50,784
5	Stone masonry foundation CM 1:6	24.4	cum	4,124	100,626
6	Plinth beam concrete M20 with formwork	6.3	cum	8,327	52,460
7	Damp proof course 50 mm, CC 1:2:4	16.2	sqm	318	5,152
3. RCC SUPERSTRUCTURE					
8	Reinforced cement concrete M25 for slab and beams	35.8	cum	7,562	270,720
9	Stair case RCC M25 incl. steps	3.7	cum	7,794	28,838
4. REINFORCEMENT					
10	TMT reinforcement bars Fe500, cut bent and placed	3524.4	kg	68	239,659
5. MASONRY					
11	External brick wall 9 inch, cement mortar 1:6	31.2	cum	4,931	153,847
12	Brickwork in CM 1:4 for internal partitions, 115mm	52.3	sqm	776	40,585
6. PLASTERING					
13	12 mm thick internal plastering CM 1:4	223.8	sqm	186	41,627
14	18 mm external plastering, sponge finish	117.8	sqm	261	30,746
7. FLOORING					
15	Vitrified tiles 2x2 ft laid on cement bed	113.2	sqm	1,094	123,841
16	Ceramic tile dado in toilets up to 7ft	26.4	sqm	834	22,018
8. WATERPROOFING					
17	APP membrane waterproofing to terrace slab	64.9	sqm	588	38,161
9. ELECTRICAL					
18	Internal concealed wiring, copper, per point	51.4	pt	697	35,826
10. PLUMBING					
19	Water supply piping CPVC, concealed	4.9	set	10,504	51,470
11. ANTI-TERMITE					
20	Termite proofing to foundation trenches	68.3	sqm	7,174	489,984
12. PAINTING					
21	Two coats acrylic emulsion on inside walls	236.6	sqm	144	34,070
22	Exterior weatherproof paint two coats	120.8	sqm	151	18,241
	TOTAL				1,865,240

Payment Schedule

Stage	Payment
Advance on agreement signing	10%
On completion of foundation	10%
On completion of plinth	8%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.