

LAKSHMI CONSTRUCTIONS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. M. Farhan | Site: Bachupally, Hyderabad | Built-up area: 1400 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Excavation for foundation in ordinary soil incl. disposal	76	cum	266	20,216
2	Backfilling with excavated earth, watered and rammed	41	cum	173	7,093
3	Sand filling under floors, 100mm	13.2	cum	1,279	16,883
2. FOUNDATION & PLINTH					
4	Plain cement concrete 1:4:8 under footings	11.5	cum	5,767	66,320
5	Random rubble masonry in cement mortar 1:6	30.6	cum	3,897	119,248
6	Plinth beam concrete M20 with formwork	7.5	cum	8,414	63,105
7	DPC 50mm thick CC 1:2:4 over plinth	16.3	sqm	318	5,183
3. RCC SUPERSTRUCTURE					
8	RCC M25 for columns, beams and roof slab	36.6	cum	8,381	306,745
9	Reinforced concrete M25 staircase waist slab	3.9	cum	7,926	30,911
4. REINFORCEMENT					
10	TMT reinforcement bars Fe500, cut bent and placed	3862.2	kg	67	258,767
5. MASONRY					
11	External brick wall 9 inch, cement mortar 1:6	31.5	cum	5,471	172,336
12	Brickwork in CM 1:4 for internal partitions, 115mm	53.7	sqm	703	37,751
6. PLASTERING					
13	Inside wall plaster 12mm	241.5	sqm	181	43,712
14	Outside wall plaster 18mm two coats	136.4	sqm	255	34,782
7. FLOORING					
15	Vitrified tile flooring 600x600 incl. skirting	121.1	sqm	1,065	128,972
16	Wall tiles in bathrooms up to 7 feet	29.4	sqm	872	25,637
8. WATERPROOFING					
17	Terrace and sunk waterproofing treatment	75.3	sqm	609	45,858
9. ELECTRICAL					
18	Electrical points incl. conduit and wiring	57.7	pt	637	36,755
10. PLUMBING					
19	CPVC water supply lines concealed incl. fittings	5.7	set	10,888	62,062
11. ANTI-TERMITE					
20	Pre-construction anti termite treatment	76.5	sqm	8,171	625,082
12. PAINTING					
21	Two coats acrylic emulsion on inside walls	230.9	sqm	127	29,324
22	Exterior weatherproof paint two coats	146.5	sqm	146	21,389
	TOTAL				2,158,131

Payment Schedule

Stage	Payment
Advance on agreement signing	10%
On completion of foundation	12%
On completion of plinth	6%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18%.