

VENKATESHWARA BUILDERS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. S. Reddy | Site: Medchal, Hyderabad | Built-up area: 1800 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1	Digging of foundation trenches, ordinary soil	87.9	cum	249	21,887
2	Refilling excavated soil around foundation	51.4	cum	138	7,093
3	Filling river sand below flooring 100 mm	17.4	cum	1,453	25,282
2. FOUNDATION & PLINTH					
4	PCC 1:4:8 with 40mm aggregate below footings	14.6	cum	5,805	84,753
5	Random rubble masonry in cement mortar 1:6	39.3	cum	3,875	152,288
6	RCC M20 for plinth beam incl. shuttering	9.4	cum	7,854	73,828
7	DPC layer above plinth level	20.1	sqm	339	6,814
3. RCC SUPERSTRUCTURE					
8	Reinforced cement concrete M25 for slab and beams	47.6	cum	8,219	391,224
9	Stair case RCC M25 incl. steps	5.4	cum	8,811	47,579
4. REINFORCEMENT					
10	TMT reinforcement bars Fe500, cut bent and placed	4620	kg	72	332,640
5. MASONRY					
11	External brick wall 9 inch, cement mortar 1:6	42	cum	5,319	223,398
12	Brickwork in CM 1:4 for internal partitions, 115mm	72.3	sqm	713	51,550
6. PLASTERING					
13	12 mm thick internal plastering CM 1:4	297	sqm	182	54,054
14	18 mm external plastering, sponge finish	177.3	sqm	241	42,729
7. FLOORING					
15	Floor tiling with vitrified tiles incl. skirting	156.6	sqm	1,037	162,394
16	Toilet dado ceramic tiling	37	sqm	831	30,747
8. WATERPROOFING					
17	Terrace and sunk waterproofing treatment	100.8	sqm	601	60,581
9. ELECTRICAL					
18	Concealed electrical wiring with copper conductor per point	78	pt	668	52,104
10. PLUMBING					
19	CPVC water supply lines concealed incl. fittings	7.5	set	11,570	86,775
11. ANTI-TERMITE					
20	Pre-construction anti termite treatment	107	sqm	6,264	670,248
12. PAINTING					
21	Interior emulsion paint two coats over primer	345.2	sqm	137	47,292
22	Outside weatherproof painting	172.5	sqm	151	26,048
	TOTAL				2,651,308

Payment Schedule

Stage	Payment
Advance on agreement signing	10%
On completion of foundation	10%
On completion of plinth	8%
On casting of roof slab	30%
On completion of brickwork & roof	26%
On finishing & handover	16%

Terms: Rates valid 30 days. Owner to provide water and electricity.