

SRI LAKSHMI BUILDERS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mrs. Ananya Rao | Site: Plot 12, Miyapur, Hyderabad | Built-up area: 1750 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1.1	Excavation for foundation in ordinary soil incl. disposal	88	cum	260	22,880
1.2	Backfilling with excavated earth, watered and rammed	52	cum	150	7,800
1.3	Sand filling under floors, 100mm	17	cum	1,400	23,800
2. FOUNDATION & PLINTH					
2.1	PCC 1:4:8 with 40mm aggregate below footings	13	cum	5,800	75,400
2.2	Size stone masonry in CM 1:6 for foundation	36	cum	4,100	147,600
2.3	Plinth beam RCC M20 incl. shuttering	6	cum	8,300	49,800
2.4	DPC 50mm CC 1:2:4 with waterproof compound	40	sqm	330	13,200
2.5	Anti-termite treatment to foundation & plinth per IS 6313	180	sqm	95	17,100
3. RCC WORK					
3.1	RCC M25 for columns incl. shuttering & curing	11.5	cum	8,200	94,300
3.2	RCC M25 for roof slab 125mm incl. shuttering	21.5	cum	8,250	177,375
3.3	RCC M20 for lintels and chajjas	3.6	cum	7,800	28,080
3.4	RCC M20 for staircase waist slab	4	cum	8,200	32,800
4. STEEL					
4.1	Binding wire	90	kg	78	7,020
4.2	TMT bars Fe500 per IS 1786, cut bent and placed incl. wastage	4600	kg	76	349,600
5. MASONRY					
5.1	9" brick wall in CM 1:6, table-moulded bricks	112	cum	5,500	616,000
5.2	4.5" partition wall in CM 1:4	228	sqm	750	171,000
6. PLASTERING					
6.1	Internal plaster 12mm CM 1:6	610	sqm	190	115,900
6.2	Ceiling plaster 6mm CM 1:4	158	sqm	170	26,860
6.3	External plaster 18mm CM 1:6, double coat	295	sqm	250	73,750
6.4	Terrace waterproofing with APP membrane incl. protection screed	155	sqm	640	99,200
7. FLOORING					
7.1	Vitrified tiles 600x600, Kajaria or Somany, laid in CM	145	sqm	1,100	159,500
7.2	Anti-skid ceramic tiles for toilets, Kajaria	26	sqm	850	22,100
7.3	Granite for kitchen platform, 18mm, Tan Brown	6	sqm	2,800	16,800
7.4	Skirting 100mm, matching floor tiles	112	rm	155	17,360
8. DOORS & WINDOWS					
8.1	Seasoned teak wood frame for main door 5"x3"	1	no	14,500	14,500
8.2	Flush doors 35mm BWR grade, Century or Greenply, painted	7	no	5,000	35,000

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
8.3	UPVC sliding windows with 5mm glass, Fenesta profile	13	sqm	3,750	48,750
8.4	MS safety grills for windows, primer + enamel	13	sqm	1,400	18,200
9. ELECTRICAL					
9.1	Concealed conduiting & wiring per point, Finolex FR copper	64	pt	690	44,160
9.2	Modular switches & sockets, Anchor Roma	64	pt	310	19,840
9.3	DB with MCBs, single phase, Havells	1	no	6,800	6,800
10. PLUMBING & SANITARY					
10.1	CPVC concealed water lines per bathroom set, Astral pipes	3	set	11,200	33,600
10.2	PVC drainage lines 110mm/75mm, Supreme	44	rm	385	16,940
10.3	EWC with concealed cistern, Hindware	3	no	8,200	24,600
10.4	Wash basins with pillar taps, Cera	4	no	3,400	13,600
10.5	OH tank 1000L triple layer, Sintex, with fittings	1	no	9,500	9,500
11. PAINTING					
11.1	Interior emulsion 2 coats over primer & putty, Asian Paints	780	sqm	140	109,200
11.2	Exterior weatherproof paint 2 coats, Apex	295	sqm	155	45,725
11.3	Enamel on grills and MS work	40	sqm	120	4,800
12. MISC					
12.1	Kitchen sink SS single bowl, Nirali, with fittings	1	no	4,200	4,200
12.2	MS main gate 4'x7' with painting	1	no	18,500	18,500
12.3	Site cleaning and debris disposal on completion	1	ls	12,000	12,000
12.4	Water & electricity for construction (borne by owner)	1	ls	0	0
	TOTAL				2,845,140

Payment Schedule

Stage	Payment
Advance on agreement signing	10%
On completion of foundation	10%
On completion of plinth	5%
On casting of roof slab	25%
On completion of brickwork & roof	30%
On finishing & handover	20%

Terms: Rates valid 30 days and are INCLUSIVE of GST @ 18% (works contract). Scope limited to items listed; any variation only via written change order signed by both parties. Owner to provide water and electricity.