

SRI SAI CONSTRUCTIONS

Bill of Quantities — Proposed Residential Building (G+0)

Client: Mr. Ravi Kumar | Site: Plot 47, Kompally, Hyderabad | Built-up area: 1800 sqft

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1. EARTHWORK					
1.1	Excavation for foundation in ordinary soil incl. disposal	92	cum	285	26,220
1.2	Backfilling with excavated earth, watered and rammed	55	cum	160	8,800
1.3	Sand filling under floors, 100mm	18	cum	1,450	26,100
2. FOUNDATION & PLINTH					
2.1	PCC 1:4:8 with 40mm aggregate below footings	14	cum	5,900	82,600
2.2	Size stone masonry in CM 1:6 for foundation	38	cum	4,200	159,600
2.3	Plinth beam RCC M20 incl. shuttering	6.5	cum	9,800	63,700
2.4	DPC 50mm CC 1:2:4 with waterproof compound	42	sqm	340	14,280
3. RCC WORK					
3.1	RCC M25 for columns incl. shuttering & curing	12	cum	9,800	117,600
3.2	RCC M25 for roof slab 125mm incl. shuttering	22.5	cum	9,800	220,500
3.3	RCC M20 for lintels and chajjas	3.8	cum	9,100	34,580
3.4	RCC M20 for staircase waist slab	4.2	cum	9,300	39,060
4. STEEL					
4.1	Binding wire	95	kg	78	7,410
4.2	TMT bars, cut bent and placed incl. wastage	4800	kg	62	297,600
5. MASONRY					
5.1	9" brick wall in CM 1:6, table-moulded bricks	118	cum	5,600	660,800
5.2	4.5" partition wall in CM 1:4	240	sqm	780	187,200
6. PLASTERING					
6.1	Internal plaster 12mm CM 1:6	640	sqm	195	124,800
6.2	Ceiling plaster 6mm CM 1:4	165	sqm	175	28,875
7. FLOORING					
7.1	Vitrified tiles 600x600 good quality, laid in CM	152	sqm	1,150	174,800
7.2	Anti-skid ceramic tiles for toilets	28	sqm	890	24,920
7.3	Granite for kitchen platform, 18mm	6.5	sqm	2,900	18,850
7.4	Skirting 100mm vitrified	118	rm	165	19,470
8. DOORS & WINDOWS					
8.1	Teak wood frame for main door 5"x3"	1	no	14,500	14,500
8.2	Flush doors 35mm commercial ply, painted	7	no	5,200	36,400
8.3	UPVC sliding windows with 5mm glass	14	sqm	3,900	54,600
8.4	MS safety grills for windows	14	sqm	1,450	20,300
9. ELECTRICAL					
9.1	Concealed conduiting & wiring per point, branded wire	68	pt	720	48,960

Item	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
9.2	Modular switches & sockets, good make	68	pt	310	21,080
9.3	DB with MCBs, single phase	1	no	6,800	6,800
10. PLUMBING & SANITARY					
10.1	CPVC concealed water lines per bathroom set	3	set	11,500	34,500
10.2	PVC drainage lines 110mm/75mm	46	rm	385	17,710
10.3	EWC with concealed cistern, standard make	3	no	8,200	24,600
10.4	Wash basins with pillar taps	4	no	3,400	13,600
10.5	OH tank 1000L triple layer with fittings	1	no	9,500	9,500
11. PAINTING					
11.1	Interior emulsion 2 coats over primer & putty	805	sqm	145	116,725
11.2	Exterior weatherproof paint 2 coats	310	sqm	165	51,150
11.3	Enamel on grills and MS work	42	sqm	120	5,040
12. MISC					
12.1	Kitchen sink SS single bowl with fittings	1	no	4,200	4,200
12.2	MS main gate 4'x7' with painting	1	no	18,500	18,500
12.3	Site cleaning and debris disposal on completion	1	ls	12,000	12,000
12.4	Water & electricity for construction (borne by owner)	1	ls	0	0
	TOTAL				2,847,930

Payment Schedule

Stage	Payment
Advance on agreement signing	20%
On completion of foundation	15%
On completion of plinth	10%
On casting of roof slab	20%
On completion of brickwork & roof	20%
On finishing & handover	15%

Terms: Rates valid 30 days. Any item not listed above will be charged extra as per actuals. Owner to provide water and electricity.